71100 #19

P58

## NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

#### REPORT 1252

## QUASI-CYLINDRICAL THEORY OF WING-BODY INTERFERENCE AT SUPERSONIC SPEEDS AND COMPARISON WITH EXPERIMENT

By JACK N. NIELSEN



1955

## REPORT 1252

# QUASI-CYLINDRICAL THEORY OF WING-BODY INTERFERENCE AT SUPERSONIC SPEEDS AND COMPARISON WITH EXPERIMENT

By JACK N. NIELSEN

Ames Aeronautical Laboratory

Moffett Field, Calif.

#### **REPORT 1252**

## QUASI-CYLINDRICAL THEORY OF WING-BODY INTERFERENCE AT SUPERSONIC SPEEDS AND COMPARISON WITH EXPERIMENT <sup>1</sup>

By JACK N. NIELSEN

#### SUMMARY

A theoretical method is presented for calculating the flow field about a wing-body combination employing bodies deviating only slightly in shape from a circular cylinder. If the combination possesses a horizontal plane of symmetry, no restrictions are required on wing plan form in the application of the method to the zero angle-of-attack condition. If the combination is lifting, the method requires that the wing leading edges be supersonic. Then the extent of the flow field that can be calculated depends on the wing aspect ratio and whether or not the trailing edges are supersonic. Two methods of calculating the flow field, the W-function method and the multipole method, are presented. The methods as presented are accurate to the order of quasi-cylindrical theory.

The method is applied to the calculation of the pressure field acting between a circular cylindrical body and a rectangular wing. These calculations are for combinations for which the effective aspect ratio of the wing panels joined together is greater than 2 and for which the effective chord-radius ratio is 4 or less. Two cases are calculated, the case in which the body remains at zero angle of attack while the wing incidence is varied and the case in which the wing remains at zero angle of incidence while the body angle of attack is varied. It was found that four Fourier components of the interference field are required to establish the pressure field, but that only one component is necessary to establish the span loading. A detailed discussion of the physical nature of the interference pressure field is given.

An experiment was performed especially for the purpose of checking the calculative examples. The investigation was performed at Mach numbers of 1.48 and 2.00 with a rectangular wing and body combination. Both the variable wing-incidence and angle-of-attack cases were covered. It was found that for sufficiently small angles, about  $2^{\circ}$  or less, the present method predicts the pressure distributions within about  $\pm 10$  percent for both cases. Important nonlinear effects were found for angles of attack and incidence of  $4^{\circ}$  to  $6^{\circ}$ , and important viscous effects were usually found where laminar boundary layers encountered shock waves.

#### INTRODUCTION

In recent years the problems of supersonic wing-body interference have occupied the attention of many workers in aerodynamics. The large amount of effort expended on the subject is a result of the important effects that interference can have on the overall aerodynamic characteristics of

wing-body combinations. The trend toward using large bodies and small wings at supersonic speeds, especially for missiles, is the prime reason for the increased importance of wing-body interference at these speeds.

Much significant work has already been done in the field. In reference 1, Spreiter has shown that when a wing-body combination is slender in the sense of his paper simple expressions for the lift and moment coefficients can be derived. These results were obtained by reducing a three-dimensional problem for the wave equation to a two-dimensional problem for Laplace's equation. Another approach is that of simplifying the differential equation by using conical boundaries. Following this approach, Browne, Friedman, and Hodes in reference 2 obtained a solution for the pressure field of a wing-body combination composed of a flat triangular wing and a cone both with a common apex. The use of all-conical boundaries reduces the problem to one of conical flow for which powerful methods of solution are available.

Several investigators have presented methods for determining the pressure field, including the effect of interference, acting on wing-body combinations employing circular fuselages and wings not necessarily slender. In reference 3, Ferrari has given an approximate method of obtaining the "interference of the wing on the streamlined body, assuming that the induced field generated by the wing is that which would exist around the wing if it were placed in the uniform stream alone." Similarly, the interference of the body on the wing has been determined. The results of Ferrari thus represent a first approximation, and while a second approximation using the method is possible in principle it appears that too much labor would be involved. Morikawa in reference 4 has obtained an approximate solution by solving a boundary-value problem and has also obtained a closed solution by approximating the three-dimensional model by a planar model. Bolton-Shaw in reference 5 has obtained a solution by satisfying boundary conditions at a finite number of points rather than over a surface.

Another method for estimating the effect of interference on the aerodynamic properties of wing-body combinations which are not necessarily slender is given in reference 6. In this reference the method is applied to determining the drag of symmetrical wing-body combinations; it is also applicable to the calculations of the lifting pressures acting on combinations employing wings with supersonic edges. In

<sup>&</sup>lt;sup>1</sup> Supersedes NACA TN 2677 "Wing-Body Interference at Supersonic Speeds With an Application to Combinations With Rectangular Wings," by Jack N. Nielsen and William C. Pitts, 1952, and NACA TN 3128 "Comparison Between Theory and Experiment for Interference Pressure Field Between Wing and Body at Supersonic Speeds," by William C. Pitts, Jack N. Nielsen, and Maurice P. Gionfriddo, 1954

reference 7, an essentially new method of solving a wide class of wing-body interference problems has been presented. The method is based on decomposing the interference of a wing-body combination into a number of Fourier components and solving the problem for each component in a manner similar to that used by von Kármán and Moore in reference 8 for bodies of revolution.

Phinney, reference 9, has compared the methods of references 3, 6, and 7 by applying each to the calculation of the pressure field acting on a circular cylinder intersected by an oblique shock wave. In reference 10 the theory of reference 7 has been applied to the computation of the pressure distributions acting on a rectangular wing and body combination with the body at zero angle of attack and the wing at incidence. In reference 11 Bailey and Phinney have applied the method of reference 7 to the calculation of the pressures on the body of a rectangular wing and body combination at angle of attack but with the wing at zero angle of attack. In reference 12 the same authors have compared their calculations with some experimental measurements made at a Mach number of 1.9. In reference 13 the experimental pressure distributions acting on a rectangular wing and body combination at Mach number 1.48 and 2.00 are extensively compared with theoretical calculations based on the method of reference 7.

In part I of the present report the theory of wing-body interference for combinations employing quasi-cylindrical bodies is presented, including recent developments not previously reported in references 7, 10, or 13. The theory is applicable to combinations at zero angle of attack with horizontal planes of symmetry or combinations at angle of attack if the wing leading edges are supersonic. II the theory is applied to the calculation of the pressures and span loadings for a rectangular wing and body combination for the case of the body at zero angle of attack and variable wing incidence and for the case of the wing at zero wing incidence and variable body angle of attack. The cal culations for the second case are more complete than hitherto. In part III extensive comparison is made between the calculations of part II and the result of experiments at Mach numbers of 1.48 and 5..00 especially designed to check the calculations.

#### SYMBOLS

a	body radius, in.
$\boldsymbol{A}$	aspect ratio of wing formed by joining exposed
	half-wings together
$\boldsymbol{c}$	chord of rectangular wing, in.
c*	effective chord-radius ratio, $rac{c}{eta a}$
$c_{2n}(x)$	strength of multipole of order $2n$ at point $x$ of body axis
$c_{ au}$	chord at wing-body juncture, in.
$c_{i}$	chord at wing tip, in.
$C_{2n}(s)$ $D_{2n}(s)$	arhitrary functions of a
$D_{2n}(s)$	arbitrary functions of s
$f_{2n}(x)$	velocity amplitude function of nth Fourier component, in./sec
$i_{W}$	wing-incidence angle, radians except where other- wise designated, positive for trailing edge down

```
modified Bessel functions of the first and second
I_{2n}(s)
K_{2n}(s)
            kinds, respectively
            \frac{L_{wc}}{L_{w}}, \alpha_{B}=0
\frac{L_{wc}}{L_{w}}, i_{w}=0
K_{w}
\boldsymbol{L}
            lift of combination back to wing trailing edge.
               lb: Laplace transform operator
L^{-1}
            inverse Laplace transform operator
L_{w}
            lift on exposed half-wings joined together, lb
            lift on exposed half-wings in combination with
L_{wc}
               body, lb
             index identifying sets of multipole solutions
m
M
            free-stream Mach number
M_{2n}(x)
             characteristic functions for obtaining multipole
               strengths
             number of Fourier component
n
             static pressure, lb/sq in.
p
             static pressure in free stream, lb/sq in.
p_o
             static pressure at any particular orifice of wing-
               body combination when \alpha_B = i_W = 0, lb/sq in.
             static pressure at wind-tunnel wall orifice, lb/sq
p_T
            pressure coefficient, \frac{p-p_1}{q_o}; -\frac{2u}{V} for theoretical
                calculations
             interference pressure coefficient due to nth
P_{2n}
                Fourier component
             free-stream dynamic pressure, lb/sq in.
q_o
             dynamic pressure based on condition at wall
q_T
                orifice of wind tunnel, lb/sq in.
             cylindrical coordinates: y=r \cos \theta, z=r \sin \theta
r,\theta,x
                (See fig. 1.)
R
             Reynolds number based on wing-chord length
R.P.
             real part
             semispan of wind-body combination, in.; Laplace
                transform of x coordinate
             axial, lateral, and vertical perturbation velocities,
u,v,w
                respectively, in./sec
V
             free-stream velocity, in./sec
             characteristic functions for calculating pressure
W_{2n}(x,r)
                coefficient
             Cartesian coordinates: x, axial coordinate; y,
x,y,z
                lateral coordinate; z, vertical coordinate, in.
                (See fig. 1.)
             body angle of attack, radians except where other-
\alpha_B
                wise designated
             upwash angle of body-alone flow, radians
\alpha_{u}
             wing angle of attack, radians
\alpha_{W}
             \sqrt{M^2-1}
             effective aspect ratio
\beta A
             Dirac delta function;
\delta(x)
             \delta(x) = 0, x \neq 0; \int_{-\infty}^{+\infty} \delta(x) dx = 1 polar angle (See fig. 1.)
θ
             taper, \frac{c_t}{c_z}
λ
              dummy variable of integration
```

sweep angle of wing leading edge

interference perturbation velocity potential φ nth Fourier component perturbation velocity  $\varphi_{2n}$ potential combination perturbation velocity potential  $\varphi_C$ wing-alone perturbation velocity potential  $\varphi_W$ wing-alone perturbation velocity potential due to  $\varphi_{W_R}$ the exposed right half of the wing wing-alone perturbation velocity potential due to the exposed left half of the wing wing-alone perturbation velocity potential due to  $\varphi_{W_B}$ the portion of wing inside the region occupied by body Laplace transform of  $\varphi$ Φ

#### SUBSCRIPTS

L lower surface of combination U upper surface of combination

#### I. GENERAL INTERFERENCE THEORY

#### PHYSICAL PRINCIPLES

Prior to a mathematical formulation of the wing-body interference problem, it is well to define interference and to explain how it arises. With a stationary wing or a stationary body in a uniform parallel flow, there are associated the wing-alone and body-alone flow fields. The wing-alone flow field does not, in general, produce flow tangential to the position to be occupied by the body surface. As a result an interference flow field must arise to cancel the flow field induced normal to the body by the wing. For this reason, the sum of the body-alone plus wing-alone flow fields will not be the flow field for the body and wing together. The difference between the flow field of the body and wing together and the sum of the body-alone and wing-alone flow fields is defined to be the interference flow field.

The effects of wing-body interference on the flow field of a wing-body combination are illustrated by considering separately the effects of each component on the others. For the purposes of this discussion figure 1 shows a wing-body combination divided into the part in front of the leading edge of the wing-body juncture, henceforth called the nose, the winged part and the part behind the wing trailing edge, henceforth called the afterbody. If the combination possesses a horizontal plane of symmetry and the angle of attack is zero, no restrictions on wing plan form are necessary. However, if the wing is twisted or cambered or if the nose is at angle of attack, then the wing leading edges must be supersonic for the following discussion to apply.




FIGURE 1.—Components of typical wing-body combination.

Effect of nose on wing.—Consider now the flow as it progresses past the body. At the body nose the flow is that around a body of revolution, and it can be treated by existing methods such as those of references 8 and 14. When the body is at angle of attack  $\alpha_B$ , there is an upwash field in the horizontal plane of symmetry of the body. If the body is sufficiently slender, the flow field in a plane at right angles to the body axis corresponds to that around a circular cylinder in a uniform stream of velocity,  $V \sin \alpha_B$ . This gives an upwash field in the horizontal plane of symmetry of the body of

 $\alpha_u = \alpha_B (1 + a^2/y^2) \tag{1}$ 

The effect of this upwash on the wing can be obtained by considering the wing to be at angle of attack and twisted according to equation (1) and by applying the formulas of supersonic wing theory. The wing pressure field so obtained is exact, within the limitations of the theory, for that section of the wing outboard of the Mach line emanating from the leading edge of the wing-body juncture. If the wing is located close to the body nose so that there is a chordwise variation in the upwash field due to the body, then the wing is effectively cambered, and the solution is more difficult. However, for most wing-body combinations it is possible to disregard the effect of the nose, and to assume that the wing is attached to a circular cylinder that extends upstream indefinitely.

Mutual effects between body and wing.—The mutual interference between the body and wing on the winged part of a combination causes an interference field acting on the body and on the wing inboard of the Mach line emanating from the leading edge of the wing-body juncture. The wing-alone flow field does not, in general, produce flow tangential to the position to be occupied by the body surface. An interference flow field must arise that cancels the velocity induced by the wing-alone flow field normal to the body while not changing the wing shape. Alternately, the origin of the interference field can be explained in the following manner. The wing and body can be thought of as sources of pressure disturbances that radiate in all directions in downstream Mach cones. The wing disturbances which radiate toward the body are, in part, reflected back by the body onto the wing and in part transmitted onto the body giving rise to interference pressures. Likewise, the disturbances originating on the body pass onto the wing and affect the pressures there. It is apparent that the determination of the interference pressure field on the body and on the wing inboard of the Mach line of the juncture is the crux of the wing-body interference problem.

Mutual effects between wing panels.—To determine the region of influence of one wing panel on another, it is necessary to trace the path of a pulse from one wing panel across the body onto the other. The path traced across the body by the pulse originating at the leading edge of the wing-body juncture is the forward boundary of the region of influence of one wing panel on the body. (See fig. 1.) It is clearly the helix intersecting all parallel elements of the cylinder at the Mach angle. The boundary crosses the top of the body a distance of  $\frac{\pi a}{2}\sqrt{M^2-1}$  downstream and reaches the opposite wing-body juncture a distance  $\pi a\sqrt{M^2-1}$  downstream. A

pulse originating at a point on one wing panel and traveling to a point on the other panel can travel around the body on its surface to the opposite juncture and then along the wing to a given point, or it can leave the body tangentially before reaching the opposite wing juncture in a straight path to the point. The second means of transmitting the impulse is shorter in distance than the first and is the one which determines the forward boundary of the region of influence of one wing panel on the other. Applying this consideration to the pulse originating at the leading edge of one wing-body juncture, it is easy to show that the forward boundary of the region of influence of one wing panel on the opposite wing panel is given by the equation

$$\frac{x}{\sqrt{M^2 - 1}} = \left(\pi - \cos^{-1}\frac{a}{y}\right)a + \sqrt{y^2 - a^2} \tag{2}$$

This boundary is also shown in figure 1, and it becomes parallel to the Mach line at distances far from the body.

Effects on the afterbody.—As far as the interference effect of the body on the wing is concerned, it is confined to the winged part of the combination, but the effect of the wing on the body is felt also on the afterbody. For a symmetrical configuration at zero angle of attack there is no downwash in the horizontal plane of symmetry and the afterbody presents no particular problem. However, behind a lifting wing there is a downwash field. If the downwash were known everywhere in the wing wake, then the wake could be considered as an extension of the wing with twist and camber. The wing wake and afterbody could then be incorporated with the winged part of the combination and treated in the same manner. However, the actual downwash pattern in the wing wake depends on the interference effect of the body on the wing. It is thus apparent that the solution of the afterbody problem requires that the interference problem for the winged part of the combination be solved first. Only the winged part of the combination is analyzed in detail in this report.

Regions of applicability of the theory.—The present interference theory can be applied to all or part of a wing-body combination depending on the configuration and the lift. If the combination is not lifting and possesses a horizontal plane of symmetry, then the interference pressure field can be determined for the entire combination. For a lifting combination with subsonic leading edges the upwash field in front of the wing makes the present method inapplicable.

For a lifting combination with supersonic leading edges several geometric factors considerably influence the difficulty of calculating the interference field or indeed the extent to which it can be calculated. The effect of one of these factors, the sweep of the trailing edge, is illustrated in figure 2 (a). A subsonic trailing edge gives rise to multiple Mach wave reflections which greatly complicate the determination of the interference field over the rear part of the wing. Another important effect limiting the applicability of the theory is illustrated in figure 2 (b). This figure indicates that the interference field behind the incident wave can influence the tip upwash field which, in turn, influences the pressure field behind the reflected wave from the tip in a complicated way.




FIGURE 2.—Classes of interference problems for lifting wing and body combinations.

(d) Tractable case.

Avoidance of this complication requires that the incident wave intersect the trailing edge rather than the wing tip. To assure this condition, the aspect ratio must be greater than a certain minimum value in accordance with the following inequality:

$$\beta A \ge \frac{4\lambda}{(1+\lambda)\left(1-\frac{\tan \Lambda}{\beta}\right)}$$

One of the simple cases of wing-body interference for a lifting wing and body combination is shown in figure 2 (c). Here the leading and trailing edges are both supersonic, and the root-chord Mach wave intersects the trailing edge. Also the wing-tip Mach wave intersects the body downstream of the wing-body juncture so that no wing-tip effects occur on the wing interference pressure field. This condition imposes the aspect-ratio inequality:

$$\beta A \ge \frac{4}{(1+\lambda)\left(1+\frac{\tan \Lambda}{\beta}\right)}$$

Under the circumstances of this figure, the interference problem proceeds as if the combination had a horizontal plane of symmetry. Any body upwash field in front of the wing can be treated as equivalent to a change in thickness distribution. The rectangular wing of aspect ratio greater than two is an example of the simple case, and it will be treated as an illustrative example in this paper.

An example of a tractable although fairly complicated case to which the present theory can be directed is shown in figure 2 (d). In region A the pressure field is determined as a pure wing-alone problem with any body upwash being treated as equivalent to a change in thickness distribution. In region B the problem is still a wing-alone problem which is complicated by upwash outboard of the tip. In region C there are body interference effects but no tip effects. In region D both effects prevail. In region E the tip has influenced the flow at the body surface and produced a secondary effect on the interference pressure field.

#### MATHEMATICAL FORMULATION OF PROBLEM

Throughout the analysis, the body radius is taken as unity and  $M^2$  is taken as 2 so that  $\beta=1$ . Any formula can be generalized to any body radius by dividing all length symbols by a, and to any Mach number by dividing all streamwise lengths by  $\beta$ , by multiplying all pressure and lift coefficients by  $\beta$ , and leaving all potentials, lift forces, and span loading unaltered. It is necessary to specify the wing alone before any detailed interference calculation can be carried out. However, in the theoretical solution of the problem the wing-alone definition is arbitrary. The flow field about the combination does not depend on the definition of the wing alone.

General decomposition of boundary-value problem.—
The general case of a combination at angle of attack with the wing at incidence as shown in figure 3 is considered. The mathematical details of the decomposition of this configuration into tractable configurations is carried out in detail in Appendix A following the suggestions in reference 15. A simplified discussion of the decomposition is now presented. The complete combination can be decomposed into three component configurations as shown in figure 4 (a) in which the wing boundary conditions are to be applied in the z=0 plane and the body conditions on the r=1





FIGURE 3.—General combination under combined effects of angle of attack and wing incidence.

cylinder. Component (1) is simply the body alone, which creates an upwash field  $\alpha_u$  in that region to be occupied by the wing in accordance with equation (1). Components (2) and (3) are combinations with wings of the same plan form; but while component (2) has a wing at angle of attack  $i_{\mathbf{w}}$ , component (3) has a wing with angle of attack  $-\alpha_{\mathbf{w}}$ . The significance of this particular method of decomposing the general wing-body problem is that component (1), the body alone, can be solved by known methods and components (2) and (3) with bodies at zero angle of attack can be solved by the methods of this report. In the wingincidence case where  $\alpha_B=0$ , only configuration (2) remains. This configuration can be decomposed into a wing-alone problem and a distorted-body problem as shown in figure 4 (b). We confine our attention to this wing-incidence case for the time being.



(a) Decomposition of general wing-body combination.(b) Decomposition for wing-incidence case.

FIGURE 4.—Decomposition of wing-body combinations into simpler combinations.

Consider now a combination with the body at zero angle of attack and let  $\varphi_{\mathcal{C}}$  be its potential. (See fig. 4(b).) This potential can be considered the sum of a wing-alone potential  $\varphi_{\mathcal{W}}$  and of an interference potential  $\varphi$ .

$$\varphi_{\mathcal{C}} = \varphi_{\mathbf{W}} + \varphi \tag{3}$$

Since the body is an infinite circular cylinder at zero angle of attack, it produces no flow field. If the body were quasicylindrical with small distortions, a potential due to the body could be included in equation (3). If the body has a horizontal plane of symmetry, the inclusion of a potential due to body distortion will not change the interference potential.

The essential problem is to determine  $\varphi$ . First, select a convenient way of extending the wing through the body to form the wing alone, thereby specifying  $\varphi_{W}$ . The wing-alone flow field in general produces velocities  $\frac{\partial \varphi_w}{\partial r}$  normal to the surface that will enclose the circular cylinder as illustrated in figure 4(b) for the region above the wing. In figure 4(b) and subsequent figures, all bodies are shown as cylinders parallel to the x axis. While the bodies of the component configurations in some cases are slightly distorted cylinders, they are nevertheless shown as true cylinders. This procedure is compatible with the fact that the boundary conditions are to be applied on a true cylinder. The value of  $\frac{\partial \varphi_w}{\partial r}$  varies with  $\theta$  and with x. This means that a body conforming to the wing-alone flow field is distorted in a complicated fashion. Now since the body must be circular, there must arise an interference potential  $\varphi$  that identically cancels  $\frac{\partial \varphi_w}{\partial r}$  at the body surface, thereby straightening it.

$$\frac{\partial \varphi}{\partial r} = -\frac{\partial \varphi_W}{\partial r} \text{ at } r = 1 \tag{4}$$

There are two other conditions to be fulfilled by  $\varphi$ . It must not distort the shape of the wing when added to  $\varphi_W$  to produce  $\varphi_C$ . Thus when  $\theta=0$ ,

$$\frac{1}{r}\frac{\partial\varphi}{\partial\theta} = 0 \tag{5}$$

or  $i_W=0$  for the interference combination as shown in figure 4(b). The last condition is that the interference potential must be zero ahead of the winged part of the combination.

$$\varphi = 0, x \le 0 \tag{6}$$

Equations (4), (5), and (6) are the essential boundary conditions on  $\varphi$ .

The normal velocity  $\frac{\partial \varphi}{\partial r}$  to be induced at the body surface by the interference potential can be analyzed at any given streamwise position as a Fourier cosine series. The amplitudes of the various Fourier cosine terms,  $f_{2n}(x)$ , vary with x, the streamwise distance. Thus,

$$\frac{\partial \varphi}{\partial r} = \sum_{n=0}^{\infty} f_{2n}(x) \cos 2n\theta = -\frac{\partial \varphi_W}{\partial r} \text{ at } r = 1$$
 (7)

Only even multiples of  $\theta$  are considered because of the vertical plane of symmetry. Consider that the interference potential is decomposed into a series of potentials such that each cancels one Fourier component of the velocity at the body surface; that is,

$$\varphi = \sum_{n=1}^{\infty} \varphi_{2n} \tag{8}$$

with

$$\frac{\partial \varphi_{2n}}{\partial r} = f_{2n}(r) \cos 2n\theta \text{ at } r = 1$$
 (9)

Then the combination giving the interference potential  $\varphi$  can be decomposed in a series of combinations, each giving one of the  $\varphi_{2n}$  values. The decomposition is illustrated in figure 5.




FIGURE 5.—Decomposition of interference combination into series of Fourier component interference combinations.

For n=0

$$\frac{\partial \varphi_o}{\partial r} = f_o(x)$$

and there is no variation of the normal velocity, pressure, or potential with  $\theta$ . Thus the first interference combination is a body of revolution. The pressure field acting on the body of such a combination can be determined by the method of reference 16. This n=0 interference combination has the very simple significance that its flow normal to the r=1 cylinder,  $\frac{\partial \varphi_{\theta}}{\partial r}$ , subtracted from  $\frac{\partial \varphi}{\partial r}$  reduces the flow across the body to zero when averaged from  $\theta=0$  to  $\theta=\pi$  at any streamwise location. For n=1,

$$\frac{\partial \varphi_2}{\partial r} = f_2(x) \cos 2\theta$$

and the normal velocity, pressure, and potential will vary as  $\cos 2\theta$ .

To summarize briefly, it has been shown that the general interference problem of a body and wing at different angles of attack can be broken down into wing-body problems with bodies at zero angle of attack as shown in figure 4 (a). Combinations with the body at zero angle of attack are decomposed into wings alone plus interference combinations as in figure 4 (b). The interference combinations are finally decomposed into their Fourier components as in figure 5.

A general method for determining the characteristics of any Fourier component will now be given. It will be shown that good accuracy can be obtained for the interference potential with few Fourier components.

#### SOLUTION BY METHOD OF W FUNCTIONS

The problem to be solved is that of a supersonic wing and body combination subject to the conditions already mentioned, but with the wing and body possibly at different angles of attack. This problem is reduced to a body-alone problem and two wing-body problems with the body at zero angle of attack as shown in figure 4 (a). The body-alone problem can be solved by existing methods such as references 8 and 14. The procedure necessary to solve either wing-body problem as given in reference 7 is now summarized together with recent improvements.

The potentials  $\varphi_C$ ,  $\varphi_W$ , and  $\varphi$  must all fulfill the equation of linearized compressible flow

$$(M^2-1)\varphi_{xx}-\varphi_{yy}-\varphi_{zz}=0 \tag{10}$$

If we restrict ourselves for the time being to the case  $M = \sqrt{2}$  and transform equation (10) to polar coordinates, we have

$$\varphi_{rr} + \frac{1}{r} \varphi_r + \frac{1}{r^2} \varphi_{\theta\theta} - \varphi_{xx} = 0 \tag{11}$$

with the coordinate system of figure 1. In solving the problem we change from the physical space, x, r,  $\theta$ , to the transformed space, s, r,  $\theta$ , by means of the Laplace transformation

$$L\left[\varphi(x)\right] \equiv \int_{a}^{\infty} e^{-sx} \varphi(x) dx = \Phi(s)$$
 (12)

With the boundary condition given by equation (6) that  $\varphi$  is zero <sup>2</sup> for  $x \le 0$ , equation (11) can be transformed to

$$\Phi_{rr} + \frac{1}{r} \Phi_r + \frac{1}{r^2} \Phi_{\theta\theta} - s^2 \Phi = 0 \tag{13}$$

Expanding  $\Phi$  in a cosine series of multiples of  $\theta$ , we can satisfy the boundary conditions given by equation (5), and since there is a vertical plane of symmetry, we can confine ourselves to even multiples of  $\theta$ . With this restriction, general solutions to equation (13) can be written

$$\Phi = \sum_{n=0}^{\infty} \cos 2n\theta \left[ C_{2n}(s) K_{2n}(sr) + D_{2n}(s) I_{2n}(sr) \right]$$
 (14)

where  $I_{2n}(sr)$  and  $K_{2n}(sr)$  are modified Bessel functions. The constants  $C_{2n}(s)$  and  $D_{2n}(s)$  are arbitrary functions of s. The functions  $I_{2n}(sr)$  can logically be eliminated at this point since from their asymptotic forms they can be shown to represent waves traveling upstream. The function  $C_{2n}(s)$  can be evaluated by means of the remaining boundary condition given by equation (7). If we let

$$F_{2n}(s) = L[f_{2n}(x)] \tag{15}$$

then

$$C_{2n}(s) = \frac{F_{2n}(s)}{sK_{2n}'(s)} \tag{16}$$

We then have as the operational solution to our problem

$$\Phi = \sum_{n=0}^{\infty} \cos 2n\theta F_{2n}(s) \frac{K_{2n}(sr)}{sK_{2n}'(s)}$$
 (17)

The solution can be split into the product of two transforms, one dependent on the particular boundary conditions as represented by the  $F_{2n}(s)$  functions and another part

independent of the boundary conditions. The inverse transform of the product of the two transforms can then be determined by the convolution integral. The part of the transform independent of the boundary condition can be thought of as defining a set of characteristic functions or influence coefficients. A tabulation of these functions allows a numerical solution of the problem for all boundary conditions.

The manner of splitting equation (17) into two transforms depends also on the existence of the inverse transforms of the parts into which it is split. Let us write equation (17) as

$$s \Phi = \sum_{n=0}^{\infty} \cos 2n\theta F_{2n}(s) e^{-s(r-1)} \left[ \frac{e^{s(r-1)} K_{2n}(sr)}{K_{2n}'(s)} + \frac{1}{\sqrt{r}} - \frac{1}{\sqrt{r}} \right]$$
(18)

With the aid of the following relationships

$$L^{-1}[F_{2n}(s)e^{-s(r-1)}] = f_{2n}(x-r+1)$$
 (19)

$$L^{-1}(s\,\Phi) = \varphi_x \tag{20}$$

and the definition of the characteristic functions

$$L^{-1} \left[ e^{s(r-1)} \frac{K_{2n}(sr)}{K_{2n}'(s)} + \frac{1}{\sqrt{r}} \right] \equiv W_{2n}(x,r)$$
 (21)

we obtain

$$\varphi_{x} = \sum_{n=0}^{\infty} \cos 2n\theta \left[ \int_{r-1}^{x} f_{2n}(\xi - r + 1) W_{2n}(x - \xi, r) d\xi - \frac{f_{2n}(x - r + 1)}{\sqrt{r}} \right]$$

$$= \sum_{n=0}^{\infty} \cos 2n\theta \left[ \int_{0}^{x - r + 1} f_{2n}(\xi) W_{2n}(x - r + 1 - \xi, r) d\xi - \frac{f_{2n}(x - r + 1)}{\sqrt{r}} \right]$$
(22)

With the aid of the  $W_{2n}(x,r)$  functions, the value of  $\varphi_x$ , and hence the pressure or potential anywhere, can be calculated from equation (22) by numerical integration for as many harmonics as desired. This result was previously given (refs. 7 and 10) for the r=1 case only as

$$\varphi_x = \sum_{n=0}^{\infty} \cos 2n\theta \left[ \int_{0}^{x} f_{2n}(\xi) W_{2n}(x-\xi) d\xi - f_{2n}(x) \right]$$
 (23)

and the  $W_{2n}(x)$  functions were tabulated for numerical calculation of the body pressure distributions only. The generalization of the  $W_{2n}(x)$  function to  $W_{2n}(x, r)$  functions by means of equation (21) is a natural extension that permits the simple calculation of the pressure anywhere in the flow field. Some mathematical properties of  $W_{2n}(x, r)$  functions and methods for their evaluation by automatic computing machinery have been studied by Dr. W. Mersman of the NACA. A résumé of his results is reported in reference 18.

Properties of the  $W_{2n}(x,r)$  functions.—Two important properties of the  $W_{2n}(x,r)$  functions that make them useful for numerical work are that they possess no singularities in the field and their magnitudes never become large. These advantages are in distinct contrast to several disadvantages of the multipole method subsequently to be described. Curves of the  $W_{2n}(x,r)$  function are presented in chart 1 for n=0,1,2, and 3 for use in numerical computations.

<sup>&</sup>lt;sup>3</sup> The condition frequently stated in deriving equation (13), that  $\phi_x=0$  for  $x=0^+$ , is not required as proven in reference (17). This is in accord with the intuitive physical idea that any step in  $\phi_x$  at the origin can be replaced by a continuous curve which for engineering purposes can have an effect different from that of the step only in a limited local region.

A simple physical picture of the  $W_{2n}(x, r)$  functions can be obtained from equation (22). Write the interference pressure coefficient <sup>3</sup> due to any harmonic as

$$P_{2n} = -\left(\frac{2}{V}\right) \frac{\partial \varphi_{2n}}{\partial x} = \frac{2 \cos 2n\theta}{V} \left[ \frac{f_{2n}(x-r+1)}{\sqrt{r}} - \int_{a}^{x-r+1} f_{2n}(\xi) W_{2n}(x-r+1-\xi,r) d\xi \right]$$
(24)

Let the velocity amplitude function be a delta function at the origin as shown in figure 6. Then




FIGURE 6.—Fourier component interference combination with "delta function" protuberence at x=0.

It is seen that physically the  $W_{2n}(x, r)$  function represents the pressure field due to a delta function in the velocity amplitude function. The first term represents an infinite pulse propagated along the Mach cone with apex at x=-1 and attenuating inversely as  $\sqrt{r}$ . The  $W_{2n}(x-r+1, r)$  term represents the overexpansion behind the bump where the pressure would be zero if the flow were two-dimensional.

Formulas for the  $W_{2n}(x, r)$  functions for small x and large x can be obtained from Laplace transform theory. In fact these results are

$$W_o(x,r) \sim \frac{1}{x^2} + 0\left(\frac{1}{x^3}\right)$$
 (26)

$$W_{2n}(x,r) \sim \frac{4(r^{2n} + r^{-2n})(4n+1)!}{2^{4n+1}(2n!)^2} \left(\frac{1}{x}\right)^{4n+2}$$
 (27)

$$W_o(x,r) \approx \frac{1}{8\sqrt{r}} \left( 3 + \frac{1}{r} \right) - \frac{3x}{128\sqrt{r}} \left( 11 + \frac{2}{r} + \frac{3}{r^2} \right) + 0(x^2)$$
 (28)

$$W_{2n}(0,r) = \frac{1}{8\sqrt{r}} \left[ (16n^2 + 3) - \frac{(16n^2 - 1)}{r} \right]$$
 (29)

It should be noted that the value of  $W_{2n}(0, r)$  is known precisely.

#### SOLUTION BY METHOD OF MULTIPOLES

Multipole types.—In references 7 and 10 a multipole method was used to determine the pressure field off the body. The singularities arising in this method, together with the loss of accuracy for the higher harmonics due to large numbers, led to the development of the  $W_{2n}(x, r)$  method just described. Since the multipole method has application to certain problems and since its connection to the  $W_{2n}(x, r)$ method is of interest, it will be given here. In the  $W_{2n}(x, r)$ method the pressure field is determined by using boundary conditions on the body surface and continuing the pressure field outward from the body. It is intuitively obvious that any quasi-cylindrical flow can be generated by distributing sources and multipoles along the body axis in variable strength. If the strength of the axial multipole distributions can be related to the body shape (velocity amplitude functions), then the entire flow field can be calculated outward from the axis.

Consider equation (14) which, with  $D_{2n}(s)$  equal to zero, is

$$\Phi = \sum_{n=0}^{\infty} C_{2n}(s) \cos 2n\theta K_{2n}(sr)$$
 (30)

This equation can be interpreted to mean that the potential is built up from a distribution of multipoles corresponding to the inverse transform of  $\cos 2n\theta K_{2n}(sr)$  along the x axis in strength  $c_{2n}(x)$ . However, there are many possible sets of multipoles corresponding to z integrals or derivatives of the set just mentioned. These are generated simply by rewriting equation (30) as

$$\Phi = \sum_{n=0}^{\infty} \left[ s^m C_{2n}(s) \right] \left[ \frac{\cos 2n\theta K_{2n}(sr)}{s^m} \right]$$
 (31)

The first term represents the axial strength function, and the second term represents the fundamental multipole solutions. For each value of the index m there is obtained a distinct set of multipole solutions. For selected values of m the multipoles have the following forms:

$$m=0$$

$$\cos 2n\theta L^{-1}[K_{2n}(sr)] = \frac{\cos 2n\theta \cosh (2n \cosh^{-1}x/r)}{\sqrt{x^2 - r^2}}; x > r$$

$$=0; x < r$$

$$m=1$$

$$\cos 2n\theta L^{-1} \left[\frac{K_{2n}(sr)}{s}\right] = \cos 2n\theta \frac{\sinh (2n \cosh^{-1}x/r)}{2n}; x > r$$

$$=0; x < r$$

$$m=2n$$

$$\cos 2n\theta L^{-1} \left[\frac{K_{2n}(sr)}{s^{2n}}\right] = \cos 2n\theta \frac{(2n)!}{(4n)!} \left(\frac{2}{r}\right)^{2n}$$

$$(x^2 - r^2)^{2n - 1/2}; x > r$$

$$=0; x < r$$

<sup>&</sup>lt;sup>3</sup> The equation for pressure coefficient to be used with equation (23) can on theoretical grounds be changed in going from the wing to the body of the configuration as discussed in reference 11. However, for simplicity, the linearized form of the Bernoulli equation is retained throughout the theoretical calculations. The contribution of the quadratic terms to the body pressure coefficient is subsequently discussed for the case of the combination at angle of attack.

For positive values of m it is clear that at the Mach cone (x=r) no nonintegrable singularities occur. For negative values of m, derivatives of the m=0 multipoles are encountered and the singularities occur on the Mach cone rather than on the axis. Since these singularities occur in the flow field, they are not well suited to numerical methods of analysis. Another set of simple multipoles with singularities on the Mach cone are those of reference 19 given by

$$\frac{r^{2n}\cos 2n\theta}{(x^2-r^2)^{2n+1/2}}$$

Multipole strengths.—The first step in determining the interference potential by the method of multipoles is to determine the multipole strength from the velocity amplitude functions. For the m=0 set of multipoles the relationship between these two quantities is already given by equation (16)

$$C_{2n}(s) = \frac{F_{2n}(s)}{sK_{2n}'(s)}$$
 (33)

If the potential at a point P as shown in figure 7 is desired, the




FIGURE 7.—General point at which potential is to be determined. multipoles must be distributed from -1 to x-r along the body axis. Since Laplace transforms must be zero for  $x \le 0$ , the axial distribution must be shifted a distance at least unity to the right by introducing  $e^{-s}$  into the transform

$$e^{-s}C_{2n}(s) = \left[\frac{1}{e^{s}sK_{2n}'(s)}\right][F_{2n}(s)]$$
 (34)

Equation (34) defines a Faltung integral involving a new set of characteristic functions given by

$$M_{2n}(x) \equiv L^{-1} \left[ \frac{1}{e^s s K_{2n}'(s)} \right]$$
 (35)

These characteristic functions have been studied in reference 7, are tabulated in table I, and are plotted in figure 8. Forming now the




FIGURE 8.—Graphical representation of  $M_{2n}(x)$  functions.

Faltung integral of equation (34) we obtain

$$c_{2n}(x-1) = \int_{a}^{x} f_{2n}(\xi) M_{2n}(x-\xi) d\xi \tag{36}$$

The function  $M_{2n}(x)$  has a square-root singularity at the origin so that  $c_{2n}(x-1)$  will be finite if  $f_{2n}(x)$  is finite. However,  $f_{2n}(x)$  may have a singularity which in confluence with the square-root singularity of  $M_{2n}(x)$  produces a singularity in  $c_{2n}(x-1)$ .

Increasing the index m by unity has the effect of integrating the set of multipoles with respect to x and of differentiating the axial strength functions by x. While this decreases the order of the singularities of the multipole solutions, it increases the order of the singularities of the axial strength functions. The highest index m that does not lead to singularities thus depends on how many nonsingular derivatives  $c_{2n}(x-1)$  possesses, which, in turn, depends on the smoothness of  $f_{2n}(x)$ . In the calculations for the wing-incidence case (ref. 7)  $f_{2n}'(x)$  has a square-root singularity at x=1 so that  $c_{2n}'(x-1)$  has a logarithmic singularity. Since  $c_{2n}(x-1)$  corresponds to m=0, it was possible to use multipole solutions of the m=1 class and still obtain integrable singularities in the axial strength functions.

Properties of the  $M_{2n}(x,r)$  functions.—The  $M_{2n}(x,r)$  functions have simple physical significance. Let the velocity amplitude function be that corresponding to a delta function as shown in figure 6. Then by equation (36)

$$c_{2n}(x-1)=M_{2n}(x)$$

Thus the  $M_{2n}(x)$  function represents the distribution along the axis of multipole strength for the m=0 set of multipoles necessary to make the velocity amplitude function a delta function. Correspondingly, it is the distribution necessary to produce a pressure field corresponding to the  $W_{2n}(x-r+1,r)$  function. Equations (25) and (30) yield the relationship between the  $W_{2n}(x,r)$  and  $M_{2n}(x)$  functions.

$$W_{2n}(x-r+1, r) = \frac{\partial}{\partial x} \int_{r-1}^{x} M_{2n}(x-\xi) \frac{\cosh\left(2n \cosh^{-1}\frac{\xi+1}{r}\right)}{\sqrt{(\xi+1)^2 - r^2}} d\xi$$

$$x > r - 1$$
(37)

Series for the  $M_{2n}(x)$  functions for small and large values of the argument have been obtained by the standard methods of Laplace transform theory in reference 7

$$M_{2n}(x) \approx -\frac{\sqrt{2}}{\pi} \left[ \frac{1}{\sqrt{x}} - \frac{(16n^2 + 3)}{4} \sqrt{x} + \frac{256n^4 - 32n^2 + 33}{96} x^{3/2} + \dots \right]$$
(38)

The square-root singularity of  $M_{2n}(x)$  at the origin is noteworthy. For the asymptotic result only a single term has been calculated

$$M_o(x) \sim -\frac{1}{x^3} \tag{39}$$

$$M_{2n}(x) \sim \frac{-16n(6n)!}{(2n!)^3 2^{6n+1}} \left(\frac{1}{x}\right)^{6n+1}$$
 (40)

Span loading and pressure coefficient.—From equation (31) the potential can be written

$$\Phi = \sum_{n=0}^{\infty} \cos 2n\theta [e^{-s}C_{2n}(s)] [K_{2n}(sr)e^{s}]$$
 (41)

so that

$$\varphi = \sum_{n=0}^{\infty} \cos 2n\theta \int_{r-1}^{x} \frac{c_{2n}(x-1-\xi) \cosh\left(2n \cosh^{-1}\frac{\xi+1}{r}\right)}{\sqrt{(\xi+1)^{2}-r^{2}}} d\xi$$
 (42)

From this result the potential can readily be obtained and hence the span loading. The pressure coefficient follows directly from equation (42) using the linearized form of Bernoulli's equation

$$P = -\frac{2}{V} \varphi_r \tag{43}$$

Thus

$$P = -\frac{2}{V} \sum_{n=0}^{\infty} \cos 2n\theta \left\{ \frac{c_{2n}(-1) \cosh\left(2n \cosh^{-1} \frac{x+1}{r}\right)}{\sqrt{(x+1)^2 - r^2}} + \right.$$

$$\int_{r-1}^{x} \frac{\partial}{\partial x} \frac{c_{2n}(x-1-\xi) \cosh\left(2n \cosh^{-1}\frac{\xi+1}{r}\right)}{\sqrt{(\xi+1)^{2}-r^{2}}} d\xi$$
 (44)

The practicability of using this result for calculating the pressures depends in the first place on the accuracy with which  $\frac{\partial}{\partial x} c_{2n}(x-1-\xi)$  can be calculated. Since this calculation depends on the  $M_{2n}(x)$  functions, which are tabulated at the present time only to the third decimal place, only three significant figures will usually be obtained for the axial strength functions. For higher harmonics and large values of x, loss of accuracy is incurred through the nature of the multipole solutions themselves. The following tabulation illustrates the point.

$\cosh(2n\cosh^{-1}x)$						
x n	0	1	· <b>2</b>	3		
1 2	1	1	1 97	1 1, 350		
$\frac{1}{3}$	1	17 31	$\begin{array}{c} 580 \\ 1920 \end{array}$	19, 600 119, 000		

Although the set of multipoles used here is not well adapted to the calculation of pressure coefficient for high harmonics and large values of x, it nevertheless is useful for calculating span loadings since only one or two harmonics are needed in this case. The difficulties of computing pressure coefficient are alleviated in part by the fact that the pressure disturbances due to higher harmonics damp out within a few downstream radii. In reference 7 the pressure coefficients were computed up to the fourth harmonic (n=3) but with some difficulty. The use of a set of multipole solutions other than the m=0 set does not hold much promise since increasing the value of m introduces singularities into the axial strength functions and decreasing the value of m introduces singularities into the multipole solutions. While these singularities into the multipole solutions.

gularities are tractable using the methods of analysis, they are not adapted to the numerical methods used herein. The method utilizing the  $W_{2n}(x,r)$  function avoids difficulties with large numbers and with singularities.

## II. APPLICATION OF THEORY TO COMBINATION OF CIRCULAR BODY AND RECTANGULAR WING

In this part of the report calculations are carried out to determine the pressure field acting on a wing-body combination employing a rectangular wing with no thickness. The calculations are first made for the body at zero angle of attack with the wing at incidence—the wing-incidence case. The calculations are then made for the body at angle of attack with the wing at zero angle of incidence—the angle-of-attack case. For the calculations attention is focused on the upper half of the combination since the experimental measurements were made for the upper half.

#### WING-INCIDENCE CASE

The complete pressure field will now be calculated. As previously mentioned, the wing alone can be specified in any convenient manner and, for the purpose of the example, the wing alone is taken as the rectangular wing extending straight through the body from side to side. Although the analysis as carried out is for  $M=\sqrt{2}$ , the results are presented in a form applicable to a range of Mach numbers. The steps in performing the calculation are: (1) to determine  $\varphi_{\overline{w}}$ , the wing-alone potential; (2) to determine the velocity amplitude functions,  $f_{2n}(x)$ ; and (3) to determine the potential or pressure, as desired, anywhere in the field. No tip effects are considered until the results are presented as a function of wing aspect ratio.

Wing-alone potential.—The wing-alone flow, exclusive of tip effects, can be determined from the Ackeret theory. The flow at a spanwise station out of the region of influence of the wing tips is illustrated in figure 9. The potential for the flow above the wing is

$$\varphi_{\mathbf{W}} = Vx \text{ when } z \ge x$$
 (45)

$$\varphi_W = Vx + i_W V(x-z)$$
 when  $z \le x$  (46)

The sidewash produced by such a potential  $\frac{\partial \varphi_w}{\partial y}$  is zero, and




FIGURE 9.—Flow field produced by wing alone.




FIGURE 10.—Variation of normal velocity induced at body surface by wing alone; unit body radius; wing-incidence case.




FIGURE 11.—Graphical representation of velocity amplitude functions; wing-incidence case.

the downwash  $\frac{\partial \varphi_W}{\partial z}$  is uniformly  $-i_W V$ . The downwash causes a flow normal to the surface r=1 in amount  $-i_W V$  sin  $\theta$ . This means that, for a body conforming to the wingalong flow, the deformation is zero at the wing-body junctures and a maximum on the top of the body. The interference combinations when added to the deformed body straighten it out Fourier component by Fourier component.

Fourier amplitudes of body normal velocity.—The Fourier amplitudes of the normal velocity induced by the wing-alone potential at the body are determined by expanding  $\frac{\partial \varphi_W}{\partial r}$  at r=1 in a Fourier cosine series of even multiples of  $\theta$ . The normal velocity distribution is shown in figure 10. For  $x \ge 1$  the body is totally immersed in the wing downwash field. With the usual equation for obtaining the Fourier amplitudes of a function, there is obtained

$$f_o(x) = \frac{2}{\pi} \int_0^{\sin^{-1}x} i_W V \sin\theta \, d\theta \tag{47}$$

$$f_{2n}(x) = \frac{4}{\pi} \int_0^{\sin^{-1}x} i_W V \sin \theta \cos 2n\theta \, d\theta \tag{48}$$

The integrations give

$$f_o(x) = \frac{2Vi_w}{\pi} \left(1 - \sqrt{1 - x^2}\right) \text{ when } x \le 1$$
 (49)

$$f_o(x) = \frac{2Vi_w}{\pi} \text{ when } x \ge 1$$
 (50)

$$f_{2n}(x) = \frac{Vi_{w}}{\pi} \left[ \frac{2\cos(2n-1)\omega}{2n-1} - \frac{2\cos(2n+1)\omega}{2n+1} - \frac{4}{4n^{2}-1} \right] \text{ when } x \le 1$$
 (51)

$$f_{2n}(x) = \frac{-4Vi_w}{\pi(4n^2 - 1)} \text{ when } x \ge 1$$
 (52)

where  $\omega = \sin^{-1} x$ . The  $f_{2n}(x)$  functions are shown in figure 11. The constant values of  $f_{2n}(x)$  for  $x \ge 1$  are noteworthy. The values of  $f_{2n}(x)$  are tabulated in table II.

Interference pressure distributions.—The interference pressure distributions have been calculated for the first four Fourier components and are presented in figure 12. In this figure the abscissa is proportional to distance behind the Mach line originating at the leading edge of the juncture, as illustrated in part (a) of the figure. Although the calculations have been carried out for  $M=\sqrt{2}$ , that is,  $\beta=1$ , and for unit radius, they are generalized to all Mach numbers and body radii by replacing x-r+1 by  $\frac{x}{\beta a}-\frac{r}{a}+1$  and  $P_{2n}$  by  $\beta P_{2n}$  as has been done in the figure. From the figure it is apparent that the cusps in the pressure distributions are propagated downstream along lines of constant  $\frac{x}{\beta a} - \frac{r}{a} + 1$  or  $x-\beta r$ ; that is, along the downstream characteristics. As the pressure distributions move outward from the body along the downstream characteristics, they are distorted and decreased in magnitude.

Increasing the order of the Fourier harmonics causes two important effects: first, the number of points of zero pressure is increased and, second, the pressure coefficient damps more rapidly. As a result of the first effect, the contributions of the higher harmonics to the combination span loading are proportionally less than their contributions to the pressure coefficient; while, as a result of the second effect, the more remote a point is from the leading edge of the wing-body juncture, the fewer the number of Fourier components that must be included to obtain its pressure coefficient accurately. All interference pressure distributions exhibit discontinuities in slope at  $\frac{x}{\beta a} - \frac{r}{a} + 1 = 1$ . This behavior is a consequence of the fact that the body becomes totally immersed in the wing-alone flow field for this condition. When the pressure distributions of the various Fourier components are added together to obtain the interference

A detailed examination of the interference pressure distribution for the first Fourier component illustrates several points of interest. The importance of the component arises from the fact that it accounts for most of the effect of interference on the span loading. The reason for this is that the pressure coefficients for n=0 are of invariable sign. The effect of the first Fourier component is to reduce the velocity induced normal to the body by the wing-alone flow field to zero averaged around the body from  $\theta=0$  to  $\theta=\pi$  at any streamwise location.

pressure distributions, the discontinuities in slope tend to

cancel so that the pressure distribution for the combination

will be smooth.




FIGURE 12.—Interference pressure distributions of various Fourier components; wing-incidence case.




FIGURE 12.—Concluded.

For purposes of comparison with the exact results for n=0, some approximate results have been included in figure 12 (a). For values of  $\frac{x}{\beta a} < 1$  on the body, the Ackeret value of  $P_o$  (twice the local stream angle divided by  $\beta$ ) is a close approximation to the true pressure coefficient. This is the result of the facts that the part of the body affecting the interference is effectively plane for points near the leading edge of the wing-body juncture and that there is no variation of any quantities with  $\theta$  so that an approximate two-dimensional situation prevails. As  $\frac{x}{\beta a}$  increases beyond unity on the body, there is a rapid decrease in the pressure coefficient below the Ackeret value due to the effect of all disturbances in front of the point in question as represented by the integral of equation (24).

In reference 7, the following approximate results were obtained for small and large values of  $\frac{x}{\beta a} - \frac{r}{a} + 1$  for the pressure coefficient:

$$\beta P_o \rightarrow \frac{2i_w}{\pi \sqrt{r}} \left( \frac{x}{\beta a} - \frac{r}{a} + 1 \right)^2$$

$$\beta P_{2n} \rightarrow \frac{4i_w}{\pi \sqrt{r}} \left( \frac{x}{\beta a} - \frac{r}{a} + 1 \right)^2 \cos 2n\theta$$
(53)

as 
$$\frac{x}{\beta a} - \frac{r}{a} + 1 \rightarrow 0$$

$$\beta P_o \rightarrow \frac{4i_W}{\pi} \left(\frac{x}{\beta a}\right)^{-1}$$

$$\beta P_{2n} \rightarrow -\frac{32i_W(4n!)(r^{2n} + r^{-2n})\cos 2n\theta}{\pi (2n!)^2 (4n^2 - 1)2^{4n+1}} \left(\frac{x}{\beta a}\right)^{-(4n+1)}$$
as  $\frac{x}{\beta a} \rightarrow \infty$ 

For  $\frac{x}{\beta a} - \frac{r}{a} + 1 \le 0.6$  equation (53) is a good approximation for n=0 although it is of little value for higher-order harmonics. There is a general tendency of  $P_o$  to approach a uniform value independent of r as  $\frac{x}{\beta a} - \frac{r}{a} + 1$  becomes large, as shown by equation (54). The damping in the characteristic direction, although initially inversely proportional to the square root of r, is ultimately independent of r.

Pressure distribution in juncture of wing-body combination.—By adding the interference pressure coefficients of the various Fourier components to that for the wing alone, the pressure distribution for the combination is obtained. The addition has been carried out for the wing-body juncture using four Fourier components and six Fourier components, and the results are presented in figure 13. The pressure coefficient with interference is less in magnitude than 2, the value without interference, showing that significant losses of lift occur in the wing-body juncture. A comparison of the results for four components and six components shows that four components give good over-all accuracy for all values of  $\frac{x}{\beta a}$  greater than 1. For small values of  $\frac{x}{\beta a}$  in the wing-body juncture, the curvature of the body insofar as the flow is




FIGURE 13.—Theoretical pressure distribution at wing-body juncture of combination using four and six Fourier components; wing-incidence case.

concerned is not large so that the body is effectively a vertical boundary on which a given distribution of normal velocity is producing an interference field. Supersonic wing theory applied to this condition gives for the net interference pressure coefficient (ref. 7).

$$\frac{\beta P}{i_W} \xrightarrow{3\pi\beta a} \frac{4x}{8\pi} \text{ when } \frac{x}{\beta a} \to 0$$
 (55)

It is clear that the calculated results can be jointed smoothly to this result. Using the result of equation (55) enables satisfactory results to be obtained with four Fourier components.

The critical region in the convergence of the solution is that near the leading edge of the wing-body juncture. The higher harmonics have their most important effect near here and rapidly damp downstream along the body. Hence more and more Fourier components would be required to get accuracy for smaller and smaller values of  $\frac{x}{\beta a}$ . However, with the result of equation (55), this extra work is unnecessary.

One point of interest in figure 13 is the fact that when  $\frac{x}{\beta a}$  equals approximately 3, the pressure coefficient increases in magnitude. This is due to the fact that for  $\frac{x}{\beta a} \ge \pi$  the influence of the opposite half-wing is felt in the wing-body juncture.

Pressure distribution on top meridian of wing-body combination.—The pressure distribution on the top meridian of the wing-body combination is obtained in the same fashion as that at the wing-body juncture, the difference being that the pressures due to the even number Fourier components have the same sign at the meridian as at the juncture, whereas the odd numbered components have reversed signs. The pressure distributions based on four and six Fourier components are shown in figure 14.

Several interesting effects are exhibited by the results. The step in the wing-alone pressure at  $\frac{x}{\beta a}$ =1 is effectively canceled by the interference pressures of the Fourier com-




FIGURE 14.—Theoretical pressure distribution on top of combination using four and six Fourier components; wing-incidence case.

ponents from  $\frac{x}{\beta a} = 1$  to  $\frac{x}{\beta a} = \pi/2$ , and for  $\frac{x}{\beta a} > \pi/2$  the pressure increases rapidly and tends toward the two-dimensional value. The effect of the interference pressure in canceling the effect of the wing alone on the top of the body from  $\frac{x}{\beta a} = 1$  to  $\frac{x}{\beta a} = \pi/2$  is to be expected since the wing of the combination can have no effect on the top of the body unless  $\frac{x}{\beta a} \ge \pi/2$ , as has been already pointed out. If an infinite number of Fourier components had been taken, the pressure coefficients would be identically zero from  $\frac{x}{\beta a} = 0$  to  $\frac{x}{\beta a} = \pi/2$ . The general behavior in this regard is evidence of the plausibility of the calculated results.

The tendency of the pressures to approach an asymptotic value is also illustrated by figure 14. This asymptotic value represented by the sum of the wing-alone pressure plus the asymptotic results for the first Fourier component is given by the following equation:

$$\frac{\beta P}{i_W} \sim -2 + \frac{4}{\pi x/\beta a} \tag{56}$$

For  $\frac{x}{\beta a} > 2.4$ , the results of this equation are in good agreement with the results of figure 14.

Some evidence is furnished from the pressure calculations for the juncture and top of the body concerning the number of Fourier components necessary for accuracy. Comparisons made in figures 13 and 14 show that about four components are sufficient and that the addition of two more is not worth the extra work.

Pressure distribution on wing of wing-body combination.— The distribution of the pressure acting on the wing of the combination can be determined in a manner similar to that for the wing-body juncture by adding to the wing-alone pressure those due to the Fourier components. The resultant pressure distribution for the wing based on four Fourier components is shown in figure 15. For small values of  $\frac{x}{\beta a}$  the higher-order oscillations in the pressure coefficient as shown in figure 13 have been ignored, and the curves have been faired through them.




FIGURE 15.—Theoretical pressure distribution acting on wing of combination; wing-incidence case.

Since the region of influence of the body on the wing is confined to the wing region downstream of the Mach lines emanating from the leading edge of the juncture, in front of this line the pressures are uniform at the two-dimensional value, and behind the line there is a decrease in the magnitude of the pressure coefficient. If the body were a perfect reflector, that is, a vertical wall of infinite extent, then there would be no pressure loss. However, the pressure pulses originating on the wing are only in part reflected by the circular body. The efficiency of the body as a reflector is discussed subsequently in connection with span loading. The tendency of the pressure to increase in magnitude near the inboard trailing edge is due to the effect of the opposite wing panel which at the wing juncture is felt downstream of the point  $\frac{x}{\beta a} = \pi$ .

Span loading.—The span load distributions for a range of rectangular wing-body combinations with the body at zero angle of attack can be determined from the pressure distributions of figures 13, 14, and 15. Since the pressure distributions of figure 15 are in a form independent of Mach number, it is convenient to define a span loading which is an integral of these distributions.

$$\frac{L}{q\alpha_{W}a^{2}} = \int_{-s/a}^{s/a} \left[ \int_{o}^{c/\beta a} \left( \frac{\beta P_{L}}{i_{W}} - \frac{\beta P_{U}}{i_{W}} \right) d \left( \frac{x}{\beta a} \right) \right] d \left( \frac{y}{a} \right) \\
= \frac{1}{a} \int_{-s}^{+s} \left[ \frac{1}{a} \int_{o}^{c} \left( \frac{P_{L}}{i_{W}} - \frac{P_{U}}{i_{W}} \right) dx \right] dy \\
= \frac{1}{a} \int_{-s}^{+s} \left[ \frac{1}{a} \int_{o}^{c} \left( \frac{-2P}{i_{W}} \right) dx \right] dy \tag{57}$$

The quantity in the square brackets is taken to be the span loading. If all distances are taken in units of the body radius, then "a" can be set equal to unity in the formulas.

The pressure results of figure 15 are for values of the effective chord-radius ratio of 4 or less and for values of the effective aspect ratio of 2 or greater. Span loadings for any combination of  $\frac{c}{\beta a}$  (or  $c^*$ ) and  $\beta A$  in these ranges can be obtained by integrating the pressure distributions. The span loading evaluations have been made for  $c^*=4$  and  $\beta A \geq 2$ . First the span loadings due to the various Fourier

components are discussed, and then the span loadings for the actual wing-body combinations are presented.

In figure 16, the contributions to the span loading for the first three Fourier components are shown. For n=0 the pressure field does not depend on  $\theta$ , being axially symmetric, and a constant loading exists on the body. However, on the wing as the spanwise distance increases there is a decrease in the span loading, due primarily to decrease in the length of chord over which the interference pressures act. The span loading due to the first Fourier component causes a loss of lift everywhere along the span.




FIGURE 16.—Theoretical span loading of various Fourier components acting on combination of body and rectangular wing having effective chord-radius ratio of 4; wing-incidence case.

A comparison of the results of figure 16 for n=0 and n=1 shows that the first Fourier component accounts almost entirely for the effect of interference on the span loading of the combination. For the body this fact is even more true than for the wing. This fact is of considerable importance since it gives a simple means of extending the lift and moment results to larger values of  $\frac{c}{\beta a}$  than those for which the pressure distributions have been calculated. Also, it suggests a simple means of minimizing the adverse effects of interference on lift as will subsequently be pointed out.

With the techniques of Laplace transform theory, it is possible to obtain asymptotic formulas for the span loadings of the various Fourier components. For the first Fourier component the following asymptotic result has been obtained by the standard methods of Laplace transform theory. (See Appendix B.)

$$-2\int_{o}^{\frac{x}{\beta a}} \left(\frac{\beta P_{o}}{i_{w}}\right) d\left(\frac{x}{\beta a}\right) = \frac{-2}{a} \int_{o}^{x} \frac{P_{o}}{i_{w}} dx \to \frac{8}{\pi} \log\left(\frac{r/2a}{x/\beta a}\right) + \frac{2}{x/\beta a}$$

when 
$$\frac{x}{\beta a} \to \infty$$
 (58)

The asymptotic result for the span loading given by this equation, when compared with the results of the exact calculations in figure 16, is seen to be slightly low. However, for values of  $\frac{c}{\beta a}$  greater than 4 the difference between the results decreases, and equation (58) thus provides a satisfactory means of extrapolating the results of the present calculations for span loading to larger values of  $\frac{c}{\beta a}$ .

The asymptotic result has also been determined for the higher-order Fourier components as a matter of interest. The span loading is

$$-2\int_{0}^{\frac{x}{\beta a}} \left(\frac{\beta P_{2n}}{i_{w}}\right) d\left(\frac{x}{\beta a}\right) = \frac{-2}{a} \int_{0}^{x} \frac{P_{2n}}{i_{w}} dx \to \frac{8\cos 2n\theta}{\pi n (4n^{2}-1)r^{2n}} - \frac{16\left(r^{2n} + \frac{1}{r^{2n}}\right) (4n-1)!\cos 2n\theta}{\pi (2n!)^{2} (4n^{2}-1)2^{4n-1} \left(\frac{x}{\beta a}\right)^{4n}} \text{ as } \frac{x}{\beta a} \to \infty \quad (59)$$

The results of equation (59) and the exact solution for n=1 in figure 16 both corroborate the fact that the span loadings of all but the first Fourier component are negligible for  $\frac{c}{\beta a} > 4$ . It is also to be noted that the contribution to the loading of the first component given by equation (58) increases without limit as  $x \to \infty$ ; whereas the span loadings of the higher-order components are finite.

To obtain the span loading for the family of combinations for which  $\frac{c}{\beta a}$ =4, it is necessary to consider the loadings of both the wing alone and the Fourier components. The necessary calculations have been carried out, and the span loadings for the family of combinations based on one and four Fourier components are both shown in figure 17. The loading due to the wing alone is also shown. No effect of wing tips has been included. It is to be noted in figure 17 that, whereas the loading on the wing due to its own pressure field is constant, there is some loss on the body because of the fact that the pressure field of the wing alone acts on the body only if  $x \ge \beta a \sin \theta$ . However, if an afterbody is included, some of the lift lost can be recovered. As has already been pointed out, the pressures due to the first Fourier components are positive on the upper half of the wing-body combination and produce a loss of lift, as figure 17 shows. When the effects of four Fourier components are taken into account, the net lift is slightly higher than that for one Fourier component, but the difference is not signifi-




FIGURE 17.—Theoretical span loading for combination of body and rectangular wing having effective chord-radius ratio of 4; wing-incidence case.

cant. For most engineering purposes, one Fourier component is sufficient for determining the span loading when  $\frac{c}{\beta a} \ge 4$ .

Some insight into the mechanism of wing-body interference can be gained by comparing the span loading for the combination with those for two reference loadings: (1) the complete reflection case for which the blanketed area of the wing acts effectively at  $i_w$ , and (2) the no-reflection case for which the blanketed area of the wing is supposed to act effectively at zero angle of attack. The span loading corresponding to the first case of complete reflection of the wing pressure pulses by the body is, in fact, the span loading marked "wing alone" in figure 17. A comparison of this curve with that based on one or four Fourier components shows that the loading given on the assumption that the wing blanketed area is fully effective in lift is too optimistic. Under the conditions of the second reference loading, the sole purpose of the blanketed area is to support lift generated by the wings. A comparison of the span loading for this case with the true loading shows that the average load on the body is well predicted, but that the loading on the wing is underestimated. A comparison of the true loading with those for the two reference cases reveals

the interesting fact that the body is somewhat less than 50 percent effective in reflection for this particular family of configurations.

Lift.—For values of  $\frac{c}{\beta a} \le 4$  the pressure distributions already presented are sufficient for obtaining span loading or lift on either the wing or body for all combinations having sufficiently large aspect ratios to avoid effects of the tips on the wing-body interference. This is the case for  $\beta A \ge 2$ . The lift results are presented in terms of a nondimensional parameter  $k_W$ , defined as the ratio of the lift on the exposed half-wings in combination (exclusive of that on the body) to that on the exposed half-wings joined together.

$$k_{\mathbf{W}} = \frac{L_{\mathbf{W}C}}{L_{\mathbf{W}}}, \ \alpha_{\mathbf{B}} = 0 \tag{60}$$

For  $\frac{c}{\beta a} > 4$  the value of  $k_w$  can be obtained by using the asymptotic form of the span loading given by equation (58).

$$k_{w}=1-\frac{8\left[c^{*}+c^{*}\log\left(\frac{2c^{*}}{c^{*}+1}\right)-\frac{\pi}{4}-\log\left(c^{*}+1\right)\right]}{\pi c^{*2}(2\beta A-1)}$$

$$c^{*}\to\infty$$
(61)

The values of  $k_w$  have been determined from the pressure distributions of figure 15 for values of  $\frac{c}{\beta a} \le 4$  and from equation (61) for values 4 of  $\frac{c}{\beta a} > 4$ . The effect of the wing tips has been taken into account by utilizing reference 20. The results are shown in figure 18 wherein  $k_w$  is given as a function




FIGURE 18.—Lift effectiveness for wing or control surface in combination with body.

of  $\frac{c}{\beta a}$  for various effective aspect ratios of 2 and greater. It should be borne in mind that the results of the figure are for a combination of body and rectangular wing or an all-movable, rectangular control surface with no gap. It is noted in the figure that the exact results for  $\frac{c}{\beta a} \le 4$  can be faired into the

<sup>&</sup>lt;sup>4</sup> In reference 10 the asymptotic analytical expressions for  $k_w$  and  $x_{cp}/c$  are not precise by virtue of an incorrect upper limit on an integral. The maximum numerical error in  $k_w$  is about 0.01 and in  $x_{cp}/c$  about 0.03 for very large values of  $c^*$ . The precise values are given in this report. Those for  $\beta A = 2$  are unchanged.

asymptotic results for  $\frac{c}{\beta a} > 4$ , thereby providing a design chart for engineering purposes for the entire range of  $\frac{c}{\beta a}$ . The curves of figure 18 illustrate the decrease of  $k_w$  as  $\frac{c}{\beta a}$  increases at constant effective aspect ratio, and the slow increase of  $k_w$  as the wing chord becomes very large. The loss of lift is most serious for  $\beta A = 2$ , being about 15 percent in the worst case.

A practical point in connection with the loss of lift on the wing due to interference is that this loss occurs no matter what the body angle of attack, even though the calculations are made for  $\alpha_B=0$ . It occurs either in the case of a wing mounted on a body or in the case of a deflected all-movable control surface. For wings with swept leading edges for which all of the wing area lies in the region affected by the interference, even larger losses than occur with rectangular wings are to be anticipated. However, the loss of lift at the design condition can, at least in principle, be largely prevented by designing the fuselage so that it conforms to the first Fourier component in the wing-alone flow. This would involve contracting the fuselage above the horizontal plane of symmetry in a rotationally symmetric fashion and expanding a like amount beneath the horizontal plane of symmetry. Whether or not such a change would improve the lift-drag ratio can best be determined by experiment.

Center of pressure.—The center-of-pressure locations have been calculated for the same range as the lift results of figure 18. The center-of-pressure location in chord lengths behind the leading edge are presented in figure 19. For large values of  $c^*$ , an asymptotic result has been calculated for  $x_{cp}/c$  using the methods of Laplace transform theory and considering only one Fourier component.

$$\frac{x_{cp}}{c} = \frac{\frac{1}{2} - \frac{1}{3\beta A} - \frac{2}{\beta A c^{*3}} \left[ \frac{2c^{*2}}{\pi} + \frac{c^{*}}{2} \log \left( \frac{2c^{*}}{c^{*} + 1} \right) - \frac{1}{2} \log (c^{*} + 1) \right]}{k_{W} \left( 1 - \frac{1}{2\beta A} \right)}$$
as  $c^{*} \to \infty$  (62)




FIGURE 19.—Center of pressure for wing or control surface in combination with body

The values of  $\frac{x_{cp}}{c}$  have been determined from the pressure distributions of figure 15 for values of  $\frac{c}{8a} \le 4$  and by equation (62) for values of  $\frac{c}{\beta a} > 4$ . The loss of lift near the tips has been taken into consideration. The exact results for  $\frac{c}{\beta a} \le 4$ have been faired into the asymptotic results for large values of  $\frac{c}{\beta a}$  by dashed curves to provide an engineering design chart covering the entire range of  $\frac{c}{\beta a}$ . It is again mentioned that this chart is applicable both to the wing of an airplane or missile or to an all-movable, rectangular control surface with no gap. The curves of figure 19 start at values of  $\frac{x_{cp}}{c}$  corresponding to those for the wing alone at  $\frac{c}{\beta a}$ =0. As  $\frac{c}{\beta a}$ increases for constant  $\beta A$ , there is a forward movement of the center of pressure because of the loss of lift due to interference which is mostly effective on the rear of the wing. For the lowest effective aspect ratio of 2 there is about a 4-percent forward movement of the center of pressure due to interference in the extreme case. For large effective aspect ratios the forward movement is not nearly so large. As the value of  $\frac{c}{\beta a}$  increases for constant  $\beta A$ , there is an asymptotic approach of the center of pressure back to the wing-alone value.

#### ANGLE-OF-ATTACK CASE

In figure 4 (a) it is shown how the flow field of a combination can be built up of a body alone and two wing-body flow fields. The first wing-body flow field ((2) of fig. 4 (a)) has been solved in the preceding section, and we now solve the second wing-body problem ((3) of fig. 4 (a)). The wing is effectively twisted so that the slope of its surface is  $\alpha_u$  as given by equation (1). It should be noted that the problem of the combination and body with a rectangular wing twisted according to the second term of equation (1) has been solved by Bailey and Phinney in reference 11 using the present theory. Their calculation is restricted to the body




FIGURE 20.—Graphical representation of velocity amplitude functions; angle-of-attack case.




FIGURE 21.—Interference pressure distributions of various Fourier components; angle-of-attack case.

and is carried out for downstream distances of  $2\beta a$  from the wing leading edge. Actually, the results of reference 11 represent the difference between the angle-of-attack and wing-incidence cases treated here and are in agreement with the present results. This agreement is, in effect, an independent check on the accuracy of the present numerical results for the interference pressure distributions.

Wing-alone potential.—The first step in the calculation is to determine the wing-alone potential. Because the wing is twisted to conform to the body upwash field, this determination is fairly tedious and has been carried out in Appendix C. The form of the wing-alone potential found in reference 11 is in agreement with those found herein for the wing-incidence and angle-of-attack cases.

Fourier amplitudes of body normal velocity.—The velocity amplitude functions for the present case were computed numerically by performing a Fourier analysis of the calculated body normal velocity distribution at a number of body cross sections. An analytical determination was made of the velocity amplitude functions by the authors of reference 11 for values of x < 2. However, for x > 2 the velocity amplitude functions are said by these authors to lead to incomplete

elliptic integrals, and no analytical determination was made. A numerical determination has been made herein for 0 < x < 4. The numerical values of the  $f_{2n}(x)$  functions for this case are tabulated in table II and plotted in figure 20 for illustrative purposes.

Interference pressure distributions.—The interference pressure distributions have been calculated by numerical integration using equation (22). The results are shown in figure 21. The interference pressure distributions are very similar to those for the wing-incidence case, being about twice as large.

Pressure distribution in juncture of wing-body combination.—The pressure distribution of the combination is obtained by adding the interference pressure coefficients to the pressure coefficients of the wing alone. The results, using four and six  $P_{2n}$  components, are shown in figure 22. This figure shows that four components give a close approximation to the linear-theory value for  $x/\beta a > 1$ . At  $x/\beta a = 0$ , the wing leading edge, linear theory with Beskin upwash theory gives exactly  $\beta P/\alpha = -4.0$ . For the region  $x/\beta a < 1$  the higher harmonics have their greatest importance, and many components would be necessary to get good accuracy.




FIGURE 21.—Continued.




FIGURE 21.—Continued.




FIGURE 21.—Concluded.




FIGURE 22.—Theoretical pressure distribution at wing-body juncture of combination using four and six Fourier components; angle-of-attack case.

However, satisfactory accuracy can be obtained by fairing a curve through this region since both end points are known.

One item of interest in figure 22 is the increase in the magnitude of  $\beta P/\alpha_B$  near point 1. This is due to the influence

of the opposite half-wing reaching the wing-body juncture at this point as shown in the sketch.

It should now be noted that the pressure distribution for the case of the body at angle of attack with the wing at zero angle of incidence is represented by the sum of cases (1) and (3) as given by figure 4 (a). However, we are neglecting the contribution of case (1) because it is small. The contribution to the pressure coefficient represented by case (1) is that due to a yawed infinite cylinder since we are neglecting nose effects. This contribution, which is clearly present in front of the wing, is

$$\left(\frac{P}{\alpha_B}\right) = \alpha_B (1 - 4\cos^2\theta) \tag{63}$$

For the juncture of the combination  $(\theta=0^\circ)$  the contribution is about 0.1 for  $\alpha_B=2^\circ$  and 0.3 for  $\alpha_B=6^\circ$ . At  $\alpha_B=2^\circ$  the effect is thus negligible compared to  $P/\alpha_B$  of about 4, and at  $\alpha_B=6^\circ$  there are definite nonlinear effects that make a precise application of linear theory inaccurate. For these reasons the contribution given by equation (63) has been neglected. For the top and bottom of the body the contributions are one-third of the foregoing and hence are also negligible.

Pressure distribution on body of wing-body combination.— The pressure distribution on the body is also obtained by adding the interference pressure coefficients to the pressure coefficients due to the wing alone. The interference pressure distribution for any value of  $\theta$  differs from that in the wing-body juncture,  $\theta = 0$ , only by a  $\cos 2n\theta$  factor. For example, in the juncture  $\cos 2n\theta$  is always +1. On top of the body,  $\theta = \pi/2$ ,  $\cos 2n\theta$  alternates between +1 and -1 as n increases. On the  $\theta = \pi/4$  meridian  $\cos 2n\theta$  has values of 0, +1, and -1, so that when n is odd  $P_{2n} = 0$ . The pressure distributions on the top meridian of the body and on the  $\theta = 45^{\circ}$  meridian of the body are shown in figures 23 and 24, respectively.




FIGURE 23.—Theoretical pressure distribution on top of combination using four and six Fourier components; angle-of-attack case.




FIGURE 24.—Theoretical pressure distribution on  $\theta$ =45° meridian of body of combination using four and six Fourier components; angle-of-attack case.

Several interesting effects are exhibited by figures 23 and 24. The step in the wing-alone pressure at  $x/\beta a=1$  in figure 23 is effectively canceled by the interference pressure from  $x/\beta a=1$  to  $x/\beta a=\pi/2$ , and for  $x/\beta a>\pi/2$  the pressure increases rapidly. The effect of the interference pressure in canceling the effect of the wing alone on the top of the body from  $x/\beta a=1$  to  $x/\beta a=\pi/2$  is to be expected since the wing of the combination can have no effect on the body in front of the Mach helix (point 1 of sketch) originating at the leading edge of the wing-body juncture. If an infinite number of components had been computed, the combination pressure

coefficients would be identically zero from  $x/\beta a=0$  to  $x/\beta a=\pi/2$ . The same effects are exhibited by figure 24 except that the wing-alone step occurs at  $x/\beta a=\sqrt{2}/2$  and the Mach helix intersects the meridian at  $x/\beta a=\pi/4$ , point 1. The Mach helix from the opposite wing panel intersects the meridian at point 2 causing an additional pressure rise. Since the region in which  $\beta P/\alpha_B=0$  is known and since the exact linear theory is well approximated by four components for large values of  $x/\beta a$ , theoretical curves of good accuracy can be faired from figures 23 and 24. The area under the high peaks in the curves near  $x/\beta a=\pi/4$  would become infinitesimal if an infinite number of interference pressure components were taken.

Pressure distribution on wing of wing-body combination.—
For the region in front of the Mach wave from the leading edge of the juncture, the calculation of pressure coefficients is just a wing-alone problem. The pressure coefficients in this region can therefore be obtained directly from the wing-alone potential as given in Appendix C. The result is

$$P = -2\alpha_B \left[ 1 + \frac{y}{(y^2 - x^2)^{3/2}} \right] \tag{64}$$

In the region behind the Mach wave the pressure coefficients were obtained directly from the  $W_{2n}(x, r)$  functions, as was done on the body. The results of these calculations for the wing pressure distributions are shown in figure 25 and are to be compared with the pressure distributions of figure 15.

Span loading.—The span loadings have been determined by graphical integration of the pressure-distribution curves of figures 21 to 25. For a combination with a value of  $c/\beta a$  of 4 the span loadings associated with the various Fourier components are shown in figure 26, which is to be compared with figure 16 for the wing-incidence case. The magnitudes for the n=0 harmonic of the angle-of-attack case are about twice those for the wing-incidence case, but otherwise the two cases are similar. The span loading including wing-alone and interference effects is shown in figure 27, which is to be compared with figure 17. The important difference is noted that the peak span loading is nearly equal to the root loading in the angle-of-attack case, but is considerably greater than the root loading in the wing-




FIGURE 25.—Theoretical pressure distribution acting on wing of combination; angle-of-attack case.




FIGURE 26.—Theoretical span loading of various Fourier components acting on combination of body and rectangular wing having effective chord-radius ratio of 4; angle-of-attack case.

incidence case. Because of the difference in the shape of the span loadings, a different trailing vortex pattern would be associated with each. No effect of wing tips is included in figures 26 and 27.

Lift.—From the theoretical wing pressure distributions of the combination the lift of the wing panels in the presence of the body can be calculated as a function of  $\beta A$  and  $c/\beta a$ . To show how the body upwash is effective in increasing the lift of the wing, a factor  $K_W$  has been calculated. This factor has been defined as

$$K_{\mathbf{w}} = \frac{L_{\mathbf{w}c}}{L_{\mathbf{w}}}; \qquad i_{\mathbf{w}} = 0 \tag{65}$$

Here  $L_{WC}$  is the lift of the panels in the presence of the body and  $L_W$  is the lift of the wing panels joined together at angle of attack  $\alpha_B$ . In calculating  $L_{WC}$  first the lift of the exposed panels as part of the wing alone must be calculated. This was done by the use of reversibility theorems described in





FIGURE 27.—Theoretical span loading for combination of body and rectangular wing having effective chord-radius ratio of 4; angle-of-attack case.

reference 21. The lift of the entire wing alone including the blanketed area was so determined. The lift of the blanketed area was then calculated from the potential function given in Appendix C and subtracted from the lift of the entire wing alone to get the lift of the panels. The loss of lift on the panels due to interference as determined by graphical integration was then subtracted to get  $L_{WC}$ . The values of  $K_W$  so calculated are shown in figure 28 (a) as a function of  $c/\beta a$  and in figure 28 (b) as a function of a/s. Figure 28 (a) shows a large effect of  $\beta A$  at constant  $c/\beta a$ ; whereas figure 28 (b) shows a small effect of  $\beta A$  at constant a/s.


In figure 28 (b) the effect of aspect ratio on  $K_W$  at a fixed value of a/s is less than the precision of the calculations as indicated by the cross-hatched area. For comparison the values of  $K_W$  calculated from slender-body theory have been included in the figure

$$K_{w} = \frac{\frac{2}{\pi} \left\{ \left( 1 + \frac{a^{4}}{s^{4}} \right) \left[ \frac{1}{2} \tan^{-1} \frac{1}{2} \left( \frac{s}{a} - \frac{a}{s} \right) + \frac{\pi}{4} \right] - \frac{a^{2}}{s^{2}} \left[ \left( \frac{s}{a} - \frac{a}{s} \right) - 2 \tan^{-1} \left( \frac{s}{a} \right) + \pi \right] \right\}}{\left( 1 - \frac{a}{s} \right)^{2}}$$
(66)



(a) Effect of chord-radius ratio.

FIGURE 28.—Lift effectiveness for rectangular wing in combination with body; angle-of-attack case.



(b) Effect of radius-semispan ratio.

FIGURE 28.—Concluded.

The close agreement between the linear-theory results for the present case and the slender-body-theory results is noteworthy since the rectangular wing and body combinations considered here are not slender. This result suggests that slender-body theory can be used for calculating lift ratios for nonslender configurations.

### III. COMPARISON OF EXPERIMENT AND THEORY FOR RECTANGULAR WING AND BODY COMBINATION

#### APPARATUS AND PROCEDURE

An investigation to evaluate the present theory was made in the Ames 1- by 3-foot supersonic wind tunnel. This wind tunnel was equipped with a flexible-plate nozzle that could be adjusted to give test-section Mach numbers from 1.2 to 2.2. The pressure measurements are obtained as photographic recordings of a multiple-tube manometer board using dibutyl phthalate as the fluid.




FIGURE 29.—Pressure distribution model (all dimensions in inches).

The sting-supported model, which is diagrammed in figure 29, is a combination consisting of a cylindrical body with an ogival nose and a rectangular, wedge-shaped wing. The dimensions of the model are given in figure 29. The wing was made 10 percent thick to minimize aeroelastic effects. It was mounted in the body by means of a set of angle blocks which enabled the flat wing surface containing the orifices to be set at  $0^{\circ}$ ,  $-1.9^{\circ}$ ,  $-3.8^{\circ}$ , and  $-5.7^{\circ}$  angles of incidence with respect to the body center line. The pressure orifices were all located on the upper surface of the model. The 47 orifices were distributed along seven spanwise stations in order to give a comparison with theory for the wing and the body. The locations of the orifices are given in table III.

Since this investigation required a comparison of the data for several Mach numbers and Reynolds numbers at the same values of  $\alpha_B$  and  $i_W$ , it was necessary to set  $\alpha_B$  and  $i_W$  accurately for each measurement. The sting support by which the model was mounted had sufficient flexibility that it was deemed necessary to have means for accurately setting the values of  $\alpha_B$  and  $i_W$  under tunnel operating conditions. The values of iw were accurately set by means of angle blocks in the body. The angle of attack was set by a special image projection device. A mirror was inserted in the schlieren system so that an image of the model was cast upon a screen. With the wind off, the model was set at the desired value of  $\alpha_B$  and the inclination of the model image was marked on the With the tunnel in operation at the desired pressure, the angle of attack of the model was adjusted until the inclination of its image was parallel to the calibration line made on the screen with the wind off. To check this method, a horizontal and vertical wire grid was placed on the tunnel window and schlieren pictures were taken of the model while the tunnel was in operation. These pictures showed that the image projection device set  $\alpha_B$  to within  $\pm 0.07^{\circ}$  of the desired value. It was especially necessary to set  $\alpha_B$ accurately for the small angles to avoid large percentage errors in the angle setting.

The model angle of attack ranged from  $+6^{\circ}$  to  $-6^{\circ}$  in  $2^{\circ}$  increments, and the wing-incidence angle ranged from  $0^{\circ}$  to  $-5.7^{\circ}$  in  $1.9^{\circ}$  increments. The test was performed at the two Mach numbers 1.48 and 2.00 and at the Reynolds numbers of 0.6, 1.2, and 1.5 million, based on the wing chord. The model was tested for all combinations of these values of the four parameters investigated.

A complete set of data in the form of P for the Reynolds numbers 0.6, 1.2, and  $1.5\times10^6$  at M=1.48 and for  $R=1.5\times10^6$  at M=2.00 is presented in table IV. These values of P are, for the most part, averages of two readings.

#### REDUCTION AND ACCURACY OF DATA

All data are reduced to the coefficient form  $(p-p_1)/q_o$ . Actually the quantity  $(p-p_T)/q_T$  was measured, and subsequent corrections were applied to change the reference static pressure to  $p_1$  ( $p_1$  is the static pressure at the particular orifice in question when  $\alpha_B = i_w = 0^\circ$ ) and the reference dynamic pressure to  $q_o$ . Since  $p_1$  includes the effects of nose thickness and stream angle, using  $p_1$  as a reference pressure minimizes these effects and essentially gives only the pressures due to the angle settings of the model. The dynamic pressure was adjusted from  $q_T$  to  $q_o$  on the basis of a previous pressure survey of the tunnel. This latter adjustment was negligible for M=1.48 and amounted to less than a 3-percent correction for M=2.00. For the purpose of comparison with theory the pressure coefficient  $(p-p_1)/q_o$  is reduced to the parameters  $\beta P/\alpha_B$  for  $i_w=0^\circ$  and  $\beta P/i_w$  for  $\alpha_B=0^\circ$ .

Two types of errors entered into the experimental investigation: systematic errors and random errors. In this paper accuracy will be taken as the ability of the experiment to give the true values without nose effect or stream angle and, hence, is a measure of the systematic errors. Precision will be taken as the ability to repeat the data and, hence, is a measure of the random errors in the experiment.

Several factors contributed random errors. The major factor was the error in the angle-of-attack setting. certainty in each angle setting was  $\pm 0.07^{\circ}$ , but each measurement was dependent upon two angle settings: the setting for the condition represented and the setting to determine the zero correction. This leads to a net uncertainty of 0.1° which would account for a 5-percent error for angles of  $\pm 2^{\circ}$ . Most of the remainder of the uncertainty in the data is due to the fact that the reference wall static pressure in the tunnel changed slightly from run to run while the total pressure remained constant. Although the magnitude of this pressure change was quite small, it was large enough compared to the small pressure differences for the 2° angle settings to cause as much as a 3-percent error. In addition to these factors, between 1-percent and 2-percent uncertainty was observed in reading the data from the manometer-board pictures.

To determine experimentally the precision of the data, a large number of repeat measurements were taken and compared. It was found that for  $\alpha_B$  or  $i_w = \pm 2^\circ$ , two independent determinations of  $\beta P/\alpha_B$  or  $\beta P/i_W$  differed from each other by  $\pm 7$  percent on the average. For  $\alpha_B$  or  $i_w = \pm 4^{\circ}$ and  $\alpha_B$  or  $i_W = \pm 6^{\circ}$ , the experimentally determined precisions of  $\beta P/\alpha_B$  and  $\beta P/i_W$  are  $\pm 4$  percent and  $\pm 2$  percent, respectively. The precision in  $\beta P/\alpha_B$  increases with the magnitude of the angle because a large part of the random error is due to the angle setting. The known major experimental errors are due to stream-angle and body-nose effects. The effect of these factors was not determined, but, as previously described, corrections were applied to minimize their effect, assuming the effects did not vary appreciably with angle-ofattack settings. This assumption should be good for the body-nose effect. However, it is not necessarily a good assumption for the stream-angle effect since the stream angle varies with vertical location in the tunnel and the model moves approximately 6 inches in a vertical direction between  $\alpha_B = +6^{\circ}$  and  $\alpha_B = -6^{\circ}$ . Since the stream-angle correction that was used was obtained for the  $\alpha_B = 0^{\circ}$  position in the tunnel, data obtained at  $\alpha_B = 0^{\circ}$  should have no appreciable error due to stream angle. For other values of α<sub>B</sub>, some error due to stream angle is possible.<sup>5</sup>

For the purposes of this paper, the important question is, "How well does theory predict the experimental data?" Direct comparisons between linear theory and experiment will be made only for  $\alpha_B = \pm 2^{\circ}$  and  $i_W = -1.9^{\circ}$  data. In figure 30 experimental pressure distributions in the wing-body juncture obtained from two independent measurements with  $i_W = -1.9^{\circ}$  and  $\alpha_B = 0^{\circ}$  are shown together with a faired curve of their average values. The  $\pm 7$ -percent limit of precision about the average value is represented by the dotted lines. The figure shows that the theoretical value generally lies between these dotted lines, and therefore the theory predicts the experimental values within the precision of the data in this example.

#### GENERAL PHYSICAL PRINCIPLES

Before the discussion of the results of the investigation in detail, it is well to give first a general physical description of the effects to be expected. Figures 31 and 32 show

<sup>&</sup>lt;sup>5</sup> A stream-angle and pressure survey of the wind tunnel in the vertical plane of symmetry indicated that stream-angle variation caused the magnitude of the experimental values of  $\beta P/\alpha_B$  to be 4 percent high on the average.




FIGURE 30.—Comparison between two independent readings of pressure distribution in wing-body juncture;  $\alpha_B=0$ ,  $i_W=1.9^\circ$ , M=1.48,  $R=1.5\times10^{\delta}$ .




FIGURE 31.—Isometric drawing of pressure distribution acting on combination of body and rectangular wing; angle-of-attack case.

qualitatively the pressure distributions to be expected on a rectangular wing and body combination for the angle-ofattack case and the wing-incidence case, respectively. The chordwise variations of the coefficient,  $\beta P/\alpha_B$  or  $\beta P/i_W$ , are shown for five stations by the shaded areas.6 These figures show that Mach cones emanating from the wing-body juncture determine the points at which the various effects of wing-body interference are felt. On the cylindrical body the pressure coefficient is zero in front of the Mach helix originating at the leading edge of the wing-body juncture. The body pressure coefficients here are taken as zero because the effects of crossflow on the body pressures are very small, as shown in connection with equation (63). However, as shown by the two stations on the body, the pressure rises abruptly behind this Mach helix, point 1, in both figures. The Mach helices from the two wing panels cross the  $\theta = \pi/2$ station simultaneously so that there is only one large increase in the magnitude of the pressure coefficient. These Mach helices cross the  $\theta=3\pi/4$  station at two different points so that beyond point 1 there is a secondary increase in the pressure coefficients at point 2. These Mach helices continue to curl around the body until they strike the wing panel at points 3, where part of the pressure disturbance continues along the wing and part of it is reflected along another Mach helix on the body, causing a further increase in the magnitude of the pressure coefficients at points 4. Another pressure disturbance originates at the trailing edge of the wing-body juncture that causes the decrease in the magnitude of the pressure coefficients noted at points 5 of the two figures.




FIGURE 32.—Isometric drawing of pressure distribution acting on combination of body and rectangular wing; wing-incidence case.

On the wing of the combination the pressure coefficient is the same as that for a wing alone in front of the Mach wave from the wing-body juncture, except that when the body is at an angle of attack the body upwash effectively twists the wing in a manner such that  $\alpha_W = \alpha_B (1 + a^2/y^2)$ . Figure 31 shows this effect of body upwash along the leading edge of the wing where the pressure coefficient decreases as y/aincreases because of the effective twist of the wing. The importance of body upwash can be seen by comparing the pressure distribution along the leading edge in figure 31 with that in figure 32. The pressure coefficient at the wing-body juncture in figure 31 is twice that in figure 32 where there is no body upwash. The pressure coefficient at any given spanwise station remains nearly constant between the wing leading edge and the Mach wave from the wing-body juncture. Behind the Mach wave, interference from the wingbody juncture causes the pressure coefficient to decrease in magnitude as shown in the two figures.

#### EFFECTS OF ANGLE OF ATTACK

Comparisons between theory and experiment for the angle-of-attack case are made in figures 33 for data at a Reynolds number of  $1.5\times10^6$  and Mach numbers of 1.48 and 2.00 with  $i_W=0^\circ$  and  $\alpha_B=\pm2^\circ$  and  $\pm6^\circ$ .

Pressure distribution in juncture of wing-body combination.—A comparison between linear theory and experiment for the pressure distribution in the wing-body juncture is made in figures 33 (a) and 33 (b) for both Mach numbers. The sketches show the pertinent Mach lines and the span-

<sup>&</sup>lt;sup>6</sup> The pressure distribution shown for the  $\theta=3\pi/4$  station on the body is identical to the pressure distribution for the  $\theta=\pi/4$  station due to the symmetry of the model.





FIGURE 33.—Pressure distributions due to angle of attack;  $R=1.5\times10^{6}$ .

wise location of the orifices.<sup>7</sup> The experimental data points from the wing surface on which a compression occurs (negative angle of attack) are represented by flagged symbols, and the data points from the surface on which an expansion occurs (positive angle of attack) are represented by unflagged symbols. The figures show that the theory predicts the magnitude of  $\beta P/\alpha_B$  about 5 percent below the average of the  $\alpha_B=\pm 2^\circ$  experimental values at M=1.48 and about 15 percent below experimental values at M=2.00. The chordwise variation is well predicted by the theory.

Linear theory predicts that the parameter  $\beta P/\alpha_B$  is independent of angle of attack. Actually it is not, and the nonlinear effects of angle of attack cause a spread in the data. It is possible to evaluate approximately the variation in the parameter  $\beta P/\alpha_B$  with angle of attack at the wing leading edge. First the upwash just in front of the leading edge was calculated using equation (1) which is based on linear theory. Then the pressure coefficients at the wing leading edge were computed using shock-expansion theory. The values of  $\beta P/\alpha_B$  for  $\alpha_B = -6^\circ$  and  $+6^\circ$  so calculated are

shown in figure 33 for values of y/a of 1.92, 2.58, and 3.92. For M=1.48 body upwash caused the shock wave to be detached from the wing in the wing-body juncture so that no calculation of the spread could be made there. For M=2.00 it was found that near the wing-body juncture the predicted spread in  $\beta P/\alpha_B$  between  $-6^{\circ}$  and  $+6^{\circ}$  was about twice the experimental spread; whereas for y/a greater than about 1.5 the experimental spread was fairly well predicted. This difference between shock-expansion theory and the experimental data in the wing-body juncture is probably due to the combination of several things. First, near the wingbody juncture the body upwash is modified by viscous effects. Second, the theoretical spread was calculated at the leading edge of the wing, and this value was assumed to apply rearward to the first orifice. This assumption is probably good beyond y/a=1.5 where the chordwise changes in pressure are small back to the first orifice, but, in the juncture, the changes in the chordwise direction are large near the wing leading edge so that this assumption is probably invalid. Third, the contribution of the body crossflow field previously mentioned is present (eq. (63)).

Another phenomenon not predicted by linear theory is shown by figure 33 (a). The linear theory predicts that the




(c) M=1.48, top meridian.

FIGURE 33.—Continued.

<sup>&</sup>lt;sup>7</sup> The location of these Mach lines is only qualitative because the calculations were made using shock-expansion theory, with the assumption that there was no local Mach number variation behind the leading edge of the wing. To simplify the sketches, the Mach belies on the body are represented as straight lines.

<sup>(</sup>d) M=2.00, top meridian.



- (e) M=1.48,  $\theta=45^{\circ}$  meridian.
- (f) M=2.00,  $\theta=45^{\circ}$  meridian.

FIGURE 33.—Continued.

Mach helix from the opposite wing panel (see sketch) should intersect the wing-body juncture at point 1, causing an increase in the magnitude of  $\beta P/\alpha_B$ . This effect is observed experimentally for negative values of  $\alpha_B$  in front of point 1 rather than exactly at point 1. The reason is that for negative values of  $\alpha_B$  a compression occurs on the orificed surface reducing the local Mach number from the free-stream Mach number, thus increasing the Mach angle and causing the Mach helix to shift forward. The result is the spread of the data shown in figure 33 (a) near point 1. This effect is not shown by figure 33 (b) because the Mach helix lies more rearward for M=2.00 so that the orifices do not extend to the Mach helix as shown by the sketch.

Figures 33 (a) and 33 (b) show that Mach number has no effect upon the magnitude of the higher-order spread due to angle of attack or upon the chordwise variation of  $\beta P/\alpha_B$ , but on the average the magnitude of  $\beta P/\alpha_B$  is about 10 percent higher for M=2.00 than for M=1.48.

Pressure distribution on top meridian of body of wing-body combination.—A comparison between the linear theory and experiment for the pressure distribution on the top meridian of the body is made in figures 33 (c) and 33 (d). These figures show that theory and experiment are in good accord




FIGURE 33.—Continued.

for  $\alpha_B = \pm 2^{\circ}$ , particularly at M=1.48. However, nonlinear effects due to  $\alpha_B$  cause a large spread between the data for  $\alpha_B = +6^{\circ}$  and  $\alpha_B = -6^{\circ}$ . All the effects predicted to occur on the body in the section of the report "General Physical Principles" are observed experimentally, but not exactly at the points predicted because of nonlinear effects. The pressure rise predicted at point 1 of figures 33 (c) and 33 (d) occurs prematurely and is less abrupt than expected for all angles of attack because of the boundary layer on the body. The variation in local Mach number causes the Mach helices to shift forward for the negative angles of attack as discussed in the section treating the wing-body juncture. The increase in the magnitude of  $\beta P/\alpha_B$  expected at point 2,  $x/\beta a = 3\pi/2$ , actually occurs at about  $x/\beta a = 4$  for  $\alpha_B = -2^\circ$ . The decrease in magnitude of  $\beta P/\alpha_B$  that is expected at point 3 actually occurs at about  $x/\beta a = 4.0$  for  $\alpha_B = -6^{\circ}$ . For the positive angles of attack the Mach helices are shifted rearward so that these effects are not observed experimentally in the range of  $x/\beta a$  measured.

Figures 33 (c) and 33 (d) show that, in general, the M=1.48 data are predicted better by the theory than are the M=2.00 data. For M=2.00 there is an unexpectedly large pressure coefficient in front of point 1 for negative




FIGURE 33.—Continued.

angles of attack. The predicted pressure coefficient due to crossflow is only about 0.1 in units of the ordinate and hence does not account for the observed effect at M=2.00. For  $\alpha_B=-2^\circ$  and M=2.00,  $\beta P/\alpha_B$  dips slightly near point 1 and then rises and overshoots the  $\alpha_B=-6^\circ$  data. This effect is due to the boundary-layer condition on the body and will be discussed in detail in the section dealing with Reynolds number effect.

Pressure distribution on  $\theta=45^{\circ}$  meridian of body of wing-body combination.—A comparison between the linear theory and experiment for the pressure distribution on the  $\theta=45^{\circ}$  meridian of the body is made in figures 33 (e) and 33 (f). Essentially the same effects are shown on this meridian as on the top meridian.

Just as for the top meridian of the body the experiment is, in general, better predicted by the theory for M=1.48 than for M=2.00, and the same boundary-layer effects are evident near point 1 for M=2.00.

Pressure distribution on wing of wing-body combination.— Experimental chordwise pressure distributions on the wing are shown in figures 33 (g) to 33 (n) for the four spanwise orifice stations y/a=1.25, 1.92, 2.58, and 3.92. In front of the Mach cone from the wing-body juncture no interference





FIGURE 33.—Continued.

is felt from the wing-body juncture so that the theoretical pressure distribution for a wing alone in the body upwash field is used in this region. Figures 33 (g) to 33 (n) show that on the average the wing-alone theory predicts magnitudes of  $\beta P/\alpha_B$  about 5 percent below the measurements for  $\alpha_B=\pm 2^\circ$  for M=1.48 and about 12 percent below the measurements for M=2.00. The spread in the data between  $\alpha_B=+6^\circ$  and  $\alpha_B=-6^\circ$  is fairly well predicted by shock-expansion theory for y/a greater than about 1.5 (figs. 33 (i) to 33(n)). At y/a=1.25 the predicted spread (not shown) is too large, just as for the wing-body juncture.

Some of the interference effects discussed in the section of the report entitled "General Physical Principles" are illustrated in figures 33 (g) to 33 (n). The interference effect from the opposite wing panel is observed in figure 33 (g) where, just in front of point 1, the same spread in the data occurs as in the wing-body juncture. According to linear theory the disturbance originating at the nearer wing-body juncture should be felt at point 2 of figures 33 (i) to 33 (m), and the magnitude of  $\beta P/\alpha_B$  should begin to decrease from the wingalone value there. These figures show that the magnitude of  $\beta P/\alpha_B$  does decrease in the neighborhood of point 2. They also show that, in general, the  $\alpha_B = +6^{\circ}$  and the  $\alpha_B = -6^{\circ}$ 



(1) 111 = 2.00; 9/4 = 0.02

FIGURE 33.—Concluded.

data come together in the neighborhood of point 2. This convergence is due to a variation in the local Mach number with  $\alpha_B$ . This is shown by the sketch in figure 33 (j)-where the disturbance from the wing-body juncture is first felt at point 3 for  $\alpha_B = -6^{\circ}$ , whereas it is first felt at point 4 for  $\alpha_B = +6^{\circ}$ . Since the magnitude of  $\beta P/\alpha_B$  begins to decrease as soon as this disturbance is felt, the magnitude of  $\beta P/\alpha_B$  begins to decrease at a smaller value of  $x/\beta a$  for  $\alpha_B = -6^{\circ}$  than for  $\alpha_B = +6^{\circ}$ , thus causing the convergence observed. The sketches in figures 33 (k) and 33 (m) show that the disturbance from the wing tip should also cause the  $\alpha_B = +6^{\circ}$  and  $\alpha_B = -6^{\circ}$  data to come together beyond point 6 in these figures. The figures show that the data not only come together but actually cross over and reverse order just beyond point 6.

The only significant effect of Mach number shown by figures 33 (g) to 33 (n) is the approximately 10-percent-larger values of  $\beta P/\alpha_B$  for M=2.00 than for M=1.48. Nearly 40 percent of this difference may be due to differences in stream angle in the wind tunnel for the two Mach numbers.

Span load distribution.—Span loading is defined for both the body and the wing as the integral (see eq. (57))

$$\int_{a}^{c/\beta a} \left[ \left( \frac{\beta P_{L}}{\alpha_{B}} \right) - \left( \frac{\beta P_{U}}{\alpha_{B}} \right) \right] d \left( \frac{x}{\beta a} \right) = - \int_{a}^{c} \left( \frac{2P}{\alpha_{B}} \right) dx \quad \text{if } a = 1$$

The experimental and theoretical results for the span loading distribution on the wing and body of the combination are presented in figure 34. No account has been taken of tip




FIGURE 34.—Span load distributions due to angle of attack;  $R=1.5\times10^6$ .

effects in calculating the span loading because the twist of the wing makes a determination of these effects a difficult wing problem. The theory is thus valid only inboard of point 2. If an approximate answer is needed, the Busemann tip solution (ref. 20) can be joined onto the span loading at point 2. Figure 34 shows that the theory is generally about 10 percent below experiment. This result is not surprising in view of the comparisons between the experimental and theoretical pressure distributions of figure 33. Of particular interest is the fact that, in general, the higher-order differences due to  $\alpha_B$  that were so large for the pressure-distribution results are negligible for the span loading distribution. The only exception is on the top of the body, y/a=0, and M=2.00, where the effects of boundary-layer and shock-wave inter-

action are large. The explanation for the independence from  $\alpha_B$  is that the higher-order effects on the top surface are compensated for by higher-order effects of the same magnitude on the lower surface so that the net loading per unit angle is very nearly independent of angle of attack.

#### EFFECT OF WING-INCIDENCE ANGLE

Comparison is made between theory and experiment for the wing-incidence case for data taken at a Reynolds number of  $1.5\times10^6$  and Mach numbers of 1.48 and 2.00 with  $\alpha_B=0^\circ$  and  $i_W=-1.9^\circ$  and  $-5.7^\circ$ . It will be remembered from the section on the accuracy of data that there is no appreciable error due to stream angle for the wing-incidence case, and the comparison between experiment and theory reflects this fact.





Figure 35.—Pressure distributions due to wing incidence;  $R = 1.5 \times 10^6$ .

Pressure distribution in wing-body junctures.—The linear theory and experimental pressure distributions in the wing-body juncture are compared in figures 35 (a) and 35 (b). The symbols in the figures are flagged to be consistent with the use of flagged symbols for negative angle-of-attack data. The figures show that the experimental values are about 5 percent below those predicted by the theory for  $i_w = -1.9^\circ$ . The magnitude of the nonlinear effects due to  $i_w$  is predicted at the leading edge by shock-expansion theory. Figures



(c) M=1.48, top meridian.


(d) M=2.00, top meridian.

FIGURE 35.—Continued.

35 (a) and 35 (b) show that the spread predicted in this manner can account for the experimental results. The premature increase in the magnitude of  $\beta P/i_W$  near point 1 is due to the effect of the opposite wing panel and variation of the local Mach number as discussed in the angle-of-attack section. No significant effect of Mach number was found on the parameter  $\beta P/i_W$ .

Pressure distribution on top meridian of body of wing-body combination.—A comparison between the linear theory and experiment for the pressure distribution on the top meridian of the body is made in figures 35 (c) and 35 (d). These figures show that theory and experiment are in good accord for  $i_w = -1.9^{\circ}$ . However, nonlinear effects due to  $i_w$  cause much larger differences between theory and experiment for  $i_w = -5.7^{\circ}$ . This is consistent with the angle-of-attack case where the higher-order effect due to  $\alpha_B$  was large for negative angles of attack.

All of the effects observed for the angle-of-attack case due to disturbances from the wing are also shown to occur for the wing-incidence case in figures 35 (c) and 35 (d). The paths of these disturbances as predicted by linear theory are shown on the sketch, and the positions at which the effects are expected to occur are shown on the abscissa.



(f) M=2.00,  $\theta=45^{\circ}$  meridian.

FIGURE 35.—Continued.

The only significant effect of Mach number apparent in figures 35 (c) and 35 (d) is the larger boundary-layer and shock-wave interaction for M=2.00 than for M=1.48 near point 1. The M=2.00 experimental data for  $i_W=-1.9^\circ$  dip and then overshoot at this point. This phenomenon is discussed in more detail in the section of the report on Reynolds number effect.

Pressure distribution on  $\theta=45^{\circ}$  meridian of body of wing-body combination.—Linear theory is compared with experimental results for the pressure distribution on the  $\theta=45^{\circ}$  meridian of the body of the combination in figures 35 (e) and 35 (f). The effects shown by the figure are consistent with those shown for the angle-of-attack case and for the wing-incidence case on the top meridian of the body.

Pressure distribution on wing of wing-body combination.— A comparison between linear theory and experiment for the pressure distribution along several spanwise stations is made in figures 35 (g) to 35 (n). The experimental data (figs. 35 (k) and 35 (l)) show that, in general,  $\beta P/i_w$  for the  $i_w = -1.9^{\circ}$  data is constant and nearly equal to -2 in front of the Mach cone. Behind the Mach cone the theory generally predicts values about 5 percent above the experimental data for  $i_w = -1.9^{\circ}$ . The higher-order effects due to  $i_w$  cause





FIGURE 35.—Continued.

larger differences between linear theory and experiment for  $i_w = -5.7^{\circ}$ . The figures show that these differences are well predicted by shock-expansion theory. The effects due to the influence of the Mach waves are the same as those discussed for the angle-of-attack case. There is no effect of Mach number evident on the wing of the wing-body combination other than that predicted by linear theory.

Span load distribution.—A comparison between the theoretical and experimental results for span load distribution on the wing and body of the combination is made in figure 36 for  $i_w = -1.9^{\circ}$ . The decrease in the span loading due to the wing tip was calculated by the method of Busemann (ref. 20). In part (a) of figure 36, interference from both the body and the wing tip is felt between points 1 and 2, but in part (b) no interference is felt between points 1 and 2, and the span loading is that of a two-dimensional wing alone.

Figure 36 shows that, in general, the experiment is 5 percent lower than the linear-theory prediction. Since all pressure measurements for the wing-incidence case were made for negative values of  $i_w$ , the experimental values used in this figure were obtained by doubling the values of  $\beta P/i_w$  obtained for  $i_w = -1.9^\circ$  rather than by considering



(i) M = 1.48, y/a = 1.92(j) M = 2.00, y/a = 1.92

FIGURE 35.—Continued.

two surfaces as for the angle-of-attack case. Since this increases the nonlinear effects of  $i_{\rm w}$  rather than minimizing them, only the  $i_{\rm w}\!=\!-1.9^{\circ}$  data (for which the nonlinear effects are small) were plotted. However, the present method is applicable to the prediction of the net span loading for larger values of  $i_{\rm w}$  because the nonlinear effects on the upper and lower surfaces tend to cancel each other, as shown for the angle-of-attack case.

#### EFFECT OF REYNOLDS NUMBER

The primary effect of Reynolds number in this investigation was on the body. Reynolds number was found to have no significant effect on the pressure distribution on the wing of the combination for the range investigated. Figure 37 shows the boundary-layer condition, as observed in schlieren pictures, on top of the body at the point of intersection with the Mach wave from the leading edge of the wing-body juncture for R=0.6 and  $1.5\times10^6$ . The transition and separation regions shown in figure 37 indicate approximately the ranges of  $\alpha_B$  and  $i_W$  in which the boundary layer changes from laminar to turbulent or separated flow at the Mach wave from the wing-body juncture. In laminar and turbulent regions the flow remains laminar or turbulent across the




FIGURE 35.—Continued.

Mach wave. Some of the Reynolds number effect shown by figure 37 may be due to changes in the turbulence level of the wind tunnel.

It is to be expected that data obtained for several angle combinations within any one of the regions shown in figure 37 would show no significant differences due to viscous effects, but that these data would differ from data in other regions. For example, for M=1.48 and  $R=0.6\times10^6$  the data for  $\alpha_{\rm B} = -2^{\rm o}$  with  $i_{\rm W} = 0^{\rm o}$  should differ from the data for  $\alpha_B = -6^{\circ}$  with  $i_W = 0^{\circ}$  because transition occurs at the shock wave for the latter case but not for the former. That there is a difference is shown in figure 38 where the pressure distributions on top of the body for these two conditions are compared. In front of the shock wave the flow is laminar for both angles of attack so that there is no difference in the two sets of data. However, for  $\alpha_B = -6^{\circ}$  transition occurs at the shock wave and the pressure rises as predicted, while for  $\alpha_R = -2^{\circ}$  laminar flow persists behind the point at which the shock is expected and the pressure rise occurs much later than predicted. In fact, the pressure rise does not occur until the transition point shown in the figure is reached, and then it tends to overshoot. This phenomenon of the delayed pressure rise was observed to occur whenever laminar flow




FIGURE 35.—Concluded.

persisted beyond the point at which a shock wave from the wing was predicted to exist. When the disturbance from the wing is an expansion wave, the pressure-coefficient curves rise approximately as predicted, regardless of the type of boundary layer. The conditions for which this delayed pressure rise was observed to occur are shown by the dotted areas in figure 37. Two other examples of this phenomenon may be seen near points 1 of figures 33 (d) and 35 (d) for  $\alpha_B = -2^{\circ}$ ,  $i_W = 0^{\circ}$  and  $\alpha_B = 0^{\circ}$ ,  $i_W = -1.9^{\circ}$ , respectively.

In figure 39, the pressure distributions on top of the body are compared for three Reynolds numbers. It is shown that data for the two highest Reynolds numbers, R=1.2 and  $1.5\times10^6$ , agree well, while the data for the lowest Reynolds number differ from those for the higher Reynolds numbers.

# COMPARISON WITH THEORY FROM OTHER SOURCES

The three theories for which numerical results are available are compared in figure 40. The theory due to Ferrari was obtained by cross-plotting from a figure in reference 22 so that the curve shown is only approximate. The theoretical curve due to Morikawa is obtained from tabulated results given in reference 4. The experimental-data region was determined by the extreme values obtained for  $\alpha_B = \pm 2^{\circ}$  for





FIGURE 36.—Span load distributions due to wing incidence;  $R=1.5\times10^6$ .

Mach numbers 1.48 and 2.00. From this figure it appears that either the theory of Morikawa or the present theory can be used to predict the pressure distribution in the juncture of a wing-body combination. Ferrari's theory predicts values that are somewhat low at the leading edge of the wing, but it appears that if numerical results were available beyond  $x/\beta a = 0.7$ , they would lie within the experimental range. For a more complete comparison of the theories of Ferrari and Nielsen, see references 9 and 23. Except for the present theory, no numerical results for the pressure distribution on the body were available for comparison.

#### CONCLUSIONS

A theory of wing-body interference for supersonic speeds has been developed. The theory was applied to the calculation of the separate effects of body angle of attack and wing incidence on the pressure distributions acting on a rectangular wing and body combination. On the basis of comparison between the theoretical predictions and experimental



- (c) M = 2.00,  $R = 0.6 \times 10^6$
- (d) M = 2.00,  $R = 1.5 \times 10^6$

FIGURE 37.—Boundary-layer condition on top meridian of body at point of intersection with Mach helix from wing.




FIGURE 38.—Effect of transition position on pressure distribution on top meridian of body; M=1.48,  $R=0.6\times10^6$ , and  $i_W=0^\circ$ .




FIGURE 39.—Effect of Reynolds number on pressure distribution on top meridian of body; M=1.48,  $\alpha_B=-6^{\circ}$ , and  $i_W=0^{\circ}$ .




FIGURE 40.—Comparison among several theoretical calculations of pressures in the wing-body juncture of the combination; angle-of-attack case.

measurements, the following conclusions are drawn:

- 1. The present theory predicts the pressure distributions due to wing incidence about 5 percent high for angles up to  $2^{\circ}$ . However, the pressure distribution due to angle of attack is predicted about 5 percent low for M=1.48 and about 10 percent low at M=2.00 for angles between  $+2^{\circ}$  and  $-2^{\circ}$ .
- 2. Nonlinear effects due to angle of attack and wing-incidence angle are large. On the wing the difference from linear theory due to nonlinear effects of angle can be predicted by shock-expansion theory, except near the wing-body juncture for the angle-of-attack case.
- 3. Span loading was shown to be predicted within  $\pm 10$  percent for both the body and the wing. The predicted span loadings are high for the wing-incidence case and low for the angle-of-attack case.
- 4. For the angle-of-attack case, the pressure coefficients on the wing are experimentally about 5 percent higher for M=2.00 than for M=1.48, when reduced to a form that is theoretically independent of Mach number. Otherwise Mach number has no important effect.
- 5. Viscous effects are important only on the body where the shock wave from the wing causes large boundary-layer and shock-wave interactions for some angle conditions.

  Ames Aeronautical Laboratory

NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS MOFFETT FIELD, CALIF., Jan. 4, 1954

#### APPENDIX A


#### DECOMPOSITION OF BOUNDARY CONDITIONS OF WING-BODY COMBINATION


A detailed analysis of the boundary conditions for a wingbody combination is now carried out for the following conditions:

- 1. The wing is a flat plate in the z=0 plane.
- 2. The body is an infinite cylinder, the r=1 cylinder.
- 3. The leading edges of the wing are supersonic.
- 4. The Mach number is  $\sqrt{2}$ .

Consider a wing-body combination corresponding to figure 4 (a) and shown in greater detail in figure 41 (a). The potentials for the flow must satisfy several conditions:

- 1. It must be a solution of the wave equation.
- 2. It must produce no flow normal to solid boundaries.
- 3. It must produce no upstream-moving disturbances.8





- (a) Parallel and crossflow.
- (b) Parallel flow.
- (c) Crossflow

FIGURE 41.—Decomposition of boundary conditions.

If  $\varphi_a$  is the potential for the complete flow about the wingbody combination, then the boundary condition on the wing is

$$\frac{\partial \varphi_a}{\partial z} = -i_W V; \quad z = 0 \tag{A1}$$

and on the body

$$\frac{\partial \varphi_a}{\partial r} = 0; \quad r = 1$$
 (A2)

The first step in the decomposition is to break  $\varphi_a$  into a potential due to flow along the x axis and one along the z axis in accordance with the superposition principle

Potential 
$$\varphi_a = \varphi_b + \varphi_c$$

$$\left(\frac{\partial \varphi}{\partial x}\right)_{\infty}: \qquad V \cos \alpha_B = V \cos \alpha_B + 0$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{\infty}: \qquad V \sin \alpha_B = 0 + V \sin \alpha_B$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{z=0^+} \text{ on wing: } -i_W V = -i_W V + 0$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{z=0^+} \text{ on body: } 0 = 0 + 0$$

The flow conditions at infinity and the prescribed normal velocities at the combination surface also obey the superposition principle.

The next steps in the decomposition are to resolve  $\varphi_b$  and  $\varphi_c$  into potentials that can easily be computed. The decomposition of  $\varphi_b$  into wing-alone and body-alone problems is illustrated in figure 41 (b).

Potential: 
$$\varphi_b = \varphi_d + \varphi_e$$

$$\left(\frac{\partial \varphi}{\partial x}\right)_{\infty}: \qquad V = 0 + V$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{\infty}: \qquad 0 = 0 + 0$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{z=0^+} \text{ on wing: } -i_W V = 0 - i_W V$$

$$\left(\frac{\partial \varphi}{\partial r}\right)_{r=1} \text{ on body: } 0 = \sum_{n=0}^{\infty} f_{2n}(x) \cos 2n\theta - \sum_{n=0}^{\infty} f_{2n}(x) \cos 2n\theta$$

The potential  $\varphi_c$  due to the wing alone at incidence  $i_W$  produces a velocity field normal to the r=1 surface to be occupied by the body. The normal velocity field is decomposed into a Fourier series. Since the wing leading edges are supersonic, we can consider the flow above the z=0 plane alone. To preserve the wing-alone boundary condition when  $\varphi_d$  is added, we must confine ourselves to cosine terms, and, because of a vertical plane of symmetry, we must retain only cosine terms of even multiples of  $\theta$  in the Fourier series. To counteract the distortion of the r=1 surface due to the wing alone, a body with opposite distortion is added in the form of  $\varphi_d$ .

 $<sup>^{</sup>f a}$  Since the surfaces on which the boundary conditions are given are parallel to the x axis, it is necessary to have this condition in order to differentiate upstream from downstream.

The decomposition of  $\varphi_c$  into three components is convenient; a component  $\varphi_f$  associated with cylindrical crossflow, a component  $\varphi_{\theta}$  due to a distorted body alone, and a component  $\varphi_{\theta}$  due to a twisted wing alone.

Potential: 
$$\varphi_c = \varphi_f + \varphi_\theta + \varphi_\theta$$

$$\left(\frac{\partial \varphi}{\partial x}\right)_{\infty}: \qquad 0 = 0 + 0 + 0$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{\infty}: \qquad \alpha_B V = \alpha_B V + 0 + 0$$

$$\left(\frac{\partial \varphi}{\partial z}\right)_{z=o^+} \text{ on wing } 0 = \alpha_B V \left(1 + \frac{1}{y^2}\right) + 0 - V \alpha_B \left(1 + \frac{1}{y^2}\right)$$

$$\left(\frac{\partial \varphi}{\partial r}\right)_{r=1} \text{ on cylinder: } 0 = 0 + \sum_{n=0}^{\infty} f_{2n}(x) \cos 2n\theta - \sum_{n=0}^{\infty} f_{2n}(x) \cos 2n\theta$$

The crossflow associated with  $\varphi_f$  causes an upwash distribution in the z=0 plane which requires an equal and opposite twisted wing to counteract it. Again the r=1 surface is distorted by the wing-alone flow field, and a cylinder with opposite distortion is introduced in the form of  $\varphi_g$  to counteract the distortion.

Two convenient cases in the wing-body interference problem are differentiated; the wing-incidence case in which  $\alpha_B=0$  but  $i_W\neq 0$  and the angle-of-attack case in which  $i_W=0$  but  $\alpha_B\neq 0$ . The wing-incidence case is represented by  $\varphi_b$  and the angle-of-attack case by  $\varphi_c$ .

## APPENDIX B

## ASYMPTOTIC SPAN LOADING FOR FIRST HARMONIC; WING-INCIDENCE CASE

The span loading for the first harmonic as given by equation (57) is

$$\int_{a}^{\frac{x}{\beta a}} \left( \frac{\beta P_L}{i_W} - \frac{\beta P_U}{i_W} \right) d\left( \frac{x}{\beta a} \right)$$
 (B1)

Let us take a=1,  $\beta=1$ , and  $P_{U}=-P_{L}=P_{o}$ ; then the span loading is

$$-2\int_{a}^{x} \left(\frac{P_{o}}{i_{\mathbf{W}}}\right) dx = \frac{4}{V_{i_{\mathbf{W}}}} \int_{a}^{x} \frac{\partial \varphi_{o}}{\partial x} dx = \frac{4\varphi_{o}}{V_{i_{\mathbf{W}}}}$$
(B2)

The method of calculating the asymptotic formula for the span loading is first to expand the Laplace transform in a series about the origin and then to take the inverse transform term by term.

From equation (17)

$$L \left[ -2 \int_{a}^{z} \left( \frac{P_{o}}{i_{\mathbf{w}}} \right) dx \right] = \left[ \frac{4F_{o}(s)}{Vi_{\mathbf{w}}} \right] \left[ \frac{K_{o}(sr)}{sK_{o}'(s)} \right]$$
(B3)

It is now necessary to find the series about the origin for the two parts of the transform of equation (B3).

From equation (47) there is obtained

$$F_o(s) = L[f_o(x)] = L\left(\frac{2}{\pi} \int_a^{\sin^{-1}x} i_w V \sin\theta \, d\theta\right)$$
 (B4)

$$F_{o}(s) = \frac{2i_{w}V}{\pi} \int_{0}^{\infty} e^{-sx} dx \int_{0}^{\sin^{-1}x} \sin\theta \, d\theta$$
$$= \frac{2i_{w}V}{\pi} \int_{0}^{\pi/2} \sin\theta \, d\theta \int_{\sin\theta}^{\infty} e^{-sx} dx$$
(B5)

$$F_o(s) = \frac{i_w V}{\pi s} \left[ \int_0^{\pi} \sin \theta \cos (is \sin \theta) d\theta + i \int_0^{\pi} \sin \theta \sin (is \sin \theta) d\theta \right]$$
(B6)

These integrals are given in terms of Anger and Weber functions as given on page 310 of reference 24.

$$\int_{0}^{\pi} \sin \theta \cos (is \sin \theta) d\theta = \pi E_{1}(is) \quad \text{(Weber function)}$$

$$\int_{\theta}^{\pi} \sin \theta \sin (is \sin \theta) d\theta = \pi J_1(is) \qquad \text{(Anger function)}$$

The value of  $F_o(s)$  is then

$$F_o(s) = \frac{i_W V}{s} [E_1(is) + iJ_1(is)]$$
 (B7)

For small values of s the Anger and Weber functions have the expansion

$$E_{1}(is) \approx \frac{2}{\pi} [1 + 0(is)^{2}]$$

$$J_{1}(is) \approx \frac{1}{2} [is + 0(is)^{3}]$$
(B8)

so that

$$F_o(s) \approx \frac{i_w V}{s} \left[ \frac{2}{\pi} - \frac{s}{2} + 0(s^2) \right]$$
 (B9)

The ratio of Bessel functions given in equation (B3) has an expansion around the origin which is a doubly infinite series of products of powers of s and log s.

$$K_o(sr) \approx -(\gamma + \log r/2) - \log s + 0(s^2) + 0(s^2 \log s)$$

$$K_o'(s) \approx -\frac{1}{s} - \frac{s}{2} \log \left(\frac{s}{2}\right) + 0(s) + 0(s^3 \log s)$$

$$K_o(sr) = -\frac{1}{s} - \frac{s}{2} \log \left(\frac{s}{2}\right) + 0(s) + 0(s^3 \log s)$$

$$\frac{K_o(sr)}{K_o'(s)} \approx s(\gamma + \log r/2) + s \log s + 0(s^3) + 0(s^3 \log^2 s) \quad (B10)$$

From equations (B9) and (B10) we get

$$L\left[-2\int_{s}^{x} \left(\frac{P_{o}}{i_{w}}\right) dx\right]$$

$$=\left(\frac{4}{Vi_{w}}\right) \left(\frac{i_{w}V}{s^{2}}\right) \left[\frac{2}{\pi} - \frac{s}{2} + 0(s^{2})\right] \left[s(\gamma + \log r/2) + s \log s + 0(s^{3} \log^{2} s)\right]$$

so that

$$L\left[-2\int_{s}^{x} \left(\frac{P_{o}}{i_{w}}\right) dx\right] = \frac{8}{\pi} \left[\frac{(\gamma + \log r/2)}{s} + \frac{\log s}{s} - \frac{\pi}{4} \log s + 0(s \log^{2} s)\right]$$
(B11)

Taking the inverse transform with the help of reference 25, page 282, we obtain the desired result.

$$-2\int_{o}^{x} \left(\frac{P_{o}}{i_{w}}\right) dx \sim \frac{8}{\pi} \left[ (\gamma + \log r/2) - \gamma - \log x + \frac{\pi}{4x} \right]$$

$$\sim \frac{8}{\pi} \left[ \log \left(\frac{r}{2x}\right) + \frac{\pi}{4x} \right]$$
 (B12)

For any Mach number and body radius

$$-2\int_{0}^{\frac{x}{\beta a}} \left(\frac{\beta P_{o}}{i_{w}}\right) d\left(\frac{x}{\beta a}\right) \sim \frac{8}{\pi} \log\left(\frac{r/a}{2x/\beta a}\right) + \frac{2}{(x/\beta a)} \text{ as } \frac{x}{\beta a} \to \infty$$
(B13)

## APPENDIX C

## DETERMINATION OF WING-ALONE POTENTIAL FOR ANGLE-OF-ATTACK CASE

The first step in calculating the potential for the wing alone will be to set up a mathematical model. Since the exposed wing of the combination operates in the body upwash field which effectively twists the wing, the wing-alone model  $^{9}$  is considered to be twisted in the manner predicted by Beskin upwash theory for  $y \ge a$ 

$$\alpha_{W} = \alpha_{B} \left( 1 + \frac{a^{2}}{y^{2}} \right) = \alpha_{B} \left( 1 + \frac{1}{y^{2}} \right)$$
 (C1)

The concealed wing may be extended through the body region in any manner but, since equation (C1) gives  $\alpha_W = 2\alpha_B$  at both wing-body junctures, it is taken as a flat plate at angle of attack  $2\alpha_B$  (see fig. 42).




FIGURE 42.—Shape of wing alone with effective twist produced by body upwash field; angle-of-attack case.

The twisting of the wing is accomplished by superimposing a series of flat-plate wings upon a basic flat-plate wing at  $\alpha_W = 2\alpha_B$  (see fig. 43). Each of the superimposed wings is at an incremental angle of attack, and each successive wing terminates at a value of y greater than the previous one. As these incremental values of  $\alpha$  become infinitesimally small, the resulting potential approaches that of a wing with the twist defined by equation (C1).

For the purposes of determining the wing-alone potential, the wing is considered to be composed of the three parts shown in figure 42: the right exposed half-wing, the left exposed half-wing, and the wing section inside the body. The perturbation velocity potential is determined for each

of these wing sections and the results added together to obtain the potential for the entire wing alone. Thus,

$$\varphi_{W} = \varphi_{W_{p}} + \varphi_{W_{r}} + \varphi_{W_{p}} \tag{C2}$$

Since the wing may be considered to be composed of an infinite number of flat, rectangular wings, the expression

$$\varphi(\alpha_{W}, y) = \frac{V\alpha_{W}}{\pi} \left( -x \cos^{-1} \frac{-y}{\sqrt{x^{2} - z^{2}}} - y \cosh^{-1} \frac{x}{\sqrt{y^{2} + z^{2}}} + z \cos^{-1} \frac{-xy}{\sqrt{y^{2} + z^{2}}} \right)$$
(C3)

from reference 6 for the velocity potential of a flat, rectangular wing will be used as the basic relation for the calculations. Equation (C3) gives the velocity potential at any point (x,y,z) due to a flat, rectangular wing at angle of attack  $\alpha_W$ , terminating at y=0, and extending to  $\infty$  along the positive y axis.<sup>10</sup>

Since the twisted wing was shown to be equivalent to a basic flat-plate wing at angle of attack  $2\alpha_B$  plus an infinite number of modifying flat-plate wings (see fig. 43), the potential of the right half-wing may be written as

$$\varphi_{W_R} = \varphi(2\alpha_B, y - 1) + \sum_{i=1}^{N} \varphi(\Delta\alpha_i, y - \eta_i)$$
 (C4)




FIGURE 43.—Formation of twisted wing by superposition of infinite number of flat plates.

Both a and B are taken as unity.

<sup>10</sup> The top and bottom wing surfaces are still considered independent.

The first term on the right in equation (C4) is the potential due to the basic exposed half-wing which terminates at the wing-body juncture, y=1, and is at angle of attack  $2\alpha_B$ . The second term is the potential of the N modifying wings each at angle of attack  $\Delta\alpha_i$  and terminating at  $y=\eta_i$  where  $1 < \eta_i \le \infty$ . Since equation (C3) is homogeneous with respect to  $\alpha$ , equation (C4) may be written

$$\varphi_{W_R} = \varphi(2\alpha_B, y-1) + \sum_{i=1}^{N} \varphi(1, y-\eta_i) \Delta \alpha_t$$
 (C5)

From equation (C1)

$$d\alpha_{\mathbf{w}} = -\frac{2\alpha_{\mathbf{B}}}{v^3} \, dy \tag{C6}$$

Therefore,

$$\varphi_{W_R} = \varphi(2\alpha_B, y-1) - 2\alpha_B \int_1^{\eta_u} \varphi(1, y-\eta) \frac{d\eta}{\eta^3}$$
 (C7)

where the limits of integration are determined by the range of y on the wing included in the fore Mach cone originating from the point for which  $\varphi_{W_R}$  is being determined. From figure 44 it is apparent from the equation of the fore Mach




FIGURE 44.—Upper value of y included in the fore Mach cone emanating from  $P_1$ ;  $\beta=1$ .

cone emanating from the arbitrary point  $P_1$  for  $\beta=1$  that

$$x_1^2 = z_1^2 + (\eta_u - y_1)^2$$

Therefore, the upper limit of integration is

$$\eta_u = y_1 + \sqrt{x_1^2 - z_1^2} \tag{C8}$$

The lower limit of integration is at the wing-body juncture, y=1. From equations (C3), (C7), and (C8),

$$\varphi_{W_{R}} = R.P. \left\{ \frac{2V\alpha_{B}}{\pi} \left[ -x\cos^{-1}\frac{-(y-1)}{\sqrt{x^{2}-z^{2}}} - (y-1)\cosh^{-1}\frac{x}{\sqrt{(y-1)^{2}+z^{2}}} + z\cos^{-1}\frac{-x(y-1)}{\sqrt{(y-1)^{2}+z^{2}}} \sqrt{x^{2}-z^{2}} \right] - \frac{2V\alpha_{B}}{\pi} \int_{1}^{y+\sqrt{x^{2}-z^{2}}} \left[ -x\cos^{-1}\frac{-(y-\eta)}{\sqrt{x^{2}-z^{2}}} - (y-\eta)\cosh^{-1}\frac{x}{\sqrt{(y-\eta)^{2}+z^{2}}} + z\cos^{-1}\frac{-x(y-\eta)}{\sqrt{(y-\eta)^{2}+z^{2}}} \sqrt{x^{2}-z^{2}} \right] \frac{d\eta}{\eta^{3}} \right\}$$
 (C9)

Carrying out the integration and combining terms gives

$$\varphi_{W_{R}} = R P \cdot \left\{ \frac{V \alpha_{B}}{\pi} \left[ -x \cos^{-1} \frac{-(y-1)}{\sqrt{x^{2}-z^{2}}} + \frac{y}{\sqrt{y^{2}+z^{2}}} - \frac{x}{\sqrt{(y-1)^{2}+z^{2}}} - \frac{xy}{(y^{2}+z^{2})\sqrt{x^{2}-y^{2}-z^{2}}} \cosh^{-1} \frac{x^{2}-y(y-1)-z^{2}}{\sqrt{x^{2}-z^{2}}} + \frac{z}{\sqrt{z^{2}+z^{2}}} \cos^{-1} \frac{-x(y-1)}{\sqrt{(y-1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}} \right] \right\}$$
(C10)

Equation (C10) gives the potential due to the exposed right half-wing. To this must be added the potentials due to the other two wing sections. The potential due to the section of the wing in the body region is simply the difference between the potentials of two flat wings at  $\alpha_w = 2\alpha_B$ . One of these wings terminates at the wing-body juncture at y=-1, figure 42, and extends (through the body) indefinitely in the positive direction. The other wing terminates at the other wing-body juncture, y=+1, and also extends indefinitely in the positive y direction. The difference between the potentials of these two wings is the potential of the wing section in the body

$$\varphi_{\mathbf{W}_{\mathbf{P}}} = \varphi(2\alpha_{\mathbf{p}}, y+1) - \varphi(2\alpha_{\mathbf{p}}, y-1) \tag{C11}$$

The expression for  $\varphi$  ( $\alpha_w$ , y) is given by equation (C3). Since the model is symmetrical about the vertical y=0

plane, the potential for the other half-wing is simply obtained by replacing y by -y in equation (C10).

$$\varphi_{\mathbf{W}_{L}} = \varphi_{\mathbf{W}_{\mathbf{P}}}(x, -y, z) \tag{C12}$$

Combining equations (C10), (C11), and (C12) gives the potential due to the entire wing alone.

$$\varphi_{w} = R.P. \frac{V\alpha_{B}}{\pi} \left\{ x \left( \cos^{-1} \frac{1-y}{\sqrt{x^{2}-z^{2}}} + \cos^{-1} \frac{1+y}{\sqrt{x^{2}-z^{2}}} \right) + \left( \frac{y}{y^{2}+z^{2}} + y - 2 \right) \cosh^{-1} \frac{x}{\sqrt{(y-1)^{2}+z^{2}}} - \left( \frac{y}{y^{2}+z^{2}} + y + 2 \right) \cosh^{-1} \frac{x}{\sqrt{(y+1)^{2}+z^{2}}} + \left( \frac{z}{y^{2}+z^{2}} - z \right) \right. \\
\left. \left[ \cos^{-1} \frac{-x(y-1)}{\sqrt{(y-1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}} + \cos^{-1} \frac{x(y+1)}{\sqrt{(y+1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}} \right] + \frac{xy}{(y^{2}+z^{2})\sqrt{x^{2}-y^{2}-z^{2}}} \left[ \cosh^{-1} \frac{x^{2}-y(y+1)-z^{2}}{\sqrt{x^{2}-z^{2}}} - \cosh^{-1} \frac{x^{2}-y(y-1)-z^{2}}{\sqrt{x^{2}-z^{2}}} \right] + 2\pi(z-x) \right\} \tag{C13}$$

Investigation of  $\varphi_W$  as given by equation (C13) reveals that there are three regions on the body in which the real part of this expression assumes different forms. A fourth region, region IV, is entirely on the wing and is, therefore, not necessary for determining the normal velocity distribution on the body. These regions are determined by three




Figure 45.—Intersection of characteristic Mach cones with z=0 plane showing corresponding regions.

characteristic Mach cones. One of the Mach cones originates on the body axis at x=0, and the other two originate at the leading edges of the two wing-body junctures (see fig. 45). The expressions for the real part of  $\varphi_W$  in the three regions on the body are:

## Region I:

$$\begin{split} \varphi_{\textit{W}} &= -\frac{V\alpha_{\textit{B}}}{\pi} \left\{ -x \left[ \cos^{-1} \frac{-(y-1)}{\sqrt{x^2 - z^2}} + \cos^{-1} \frac{(y+1)}{\sqrt{x^2 - z^2}} \right] - \right. \\ & \left. \left( \frac{y}{y^2 + z^2} + y - 2 \right) \cosh^{-1} \frac{x}{\sqrt{(y-1)^2 + z^2}} + \right. \end{split}$$

$$\left(\frac{y}{y^{2}+z^{2}}+y+2\right)\cosh^{-1}\frac{x}{\sqrt{(y+1)^{2}+z^{2}}}+\left(z-\frac{z}{y^{2}+z^{2}}\right)$$

$$\left[\cos^{-1}\frac{-x(y-1)}{\sqrt{(y-1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}}+\cos^{-1}\frac{x(y+1)}{\sqrt{(y+1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}}\right]+$$

$$\frac{xy}{(y^{2}+z^{2})\sqrt{x^{2}-y^{2}-z^{2}}}\left[\cosh^{-1}\frac{x^{2}-z^{2}-y(y-1)}{\sqrt{x^{2}-z^{2}}}-\cos^{-1}\frac{x^{2}-z^{2}-y(y+1)}{\sqrt{x^{2}-z^{2}}}\right]-2(z-x)\pi\right\}$$
(C14)

Region II:

$$\varphi_{W} = -\frac{V\alpha_{B}}{\pi} \left[ -x \cos^{-1} \frac{-(y-1)}{\sqrt{x^{2}-z^{2}}} - \left( \frac{y}{y^{2}+z^{2}} + y - 2 \right) \cosh^{-1} \frac{x}{\sqrt{(y-1)^{2}+z^{2}}} - \left( \frac{z}{y^{2}+z^{2}} - z \right) \cos^{-1} \frac{-x(y-1)}{\sqrt{(y-1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}} + \frac{xy}{(y^{2}+z^{2})\sqrt{x^{2}-y^{2}-z^{2}}} \cosh^{-1} \frac{x^{2}-z^{2}-y(y-1)}{\sqrt{x^{2}-z^{2}}} - 2(z-x)\pi \right]$$
(C15)


Region III:

$$\varphi_{W} = -\frac{V\alpha_{B}}{\pi} \left[ -x \cos^{-1} \frac{-(y-1)}{\sqrt{x^{2}-z^{2}}} - \frac{x}{\sqrt{(y-1)^{2}+z^{2}}} - \frac{x}{\sqrt{(y-1)^{2}+z^{2}}} - \frac{x}{\sqrt{(y-1)^{2}+z^{2}}} - \frac{x}{\sqrt{(y-1)^{2}+z^{2}}\sqrt{x^{2}-z^{2}}} + \frac{xy}{(y^{2}+z^{2})\sqrt{y^{2}+z^{2}-x^{2}}} \cos^{-1} \frac{x^{2}-z^{2}-y(y-1)}{\sqrt{x^{2}-z^{2}}} - 2(z-x)\pi \right]$$
(C16)


#### REFERENCES

- Spreiter, John R.: The Aerodynamic Forces on Slender Plane- and Cruciform-Wing and Body Combinations. NACA Rep. 962, 1950. (Formerly NACA TN's 1662 and 1897.)
- Browne, S. H., Friedman, L., and Hodes, I.: A Wing-Body Problem in a Supersonic Conical Flow. Jour. Aero. Sci., vol. 15, no. 8, Aug. 1948, pp. 443-452.
- Ferrari, Carlo: Interference Between Wing and Body at Supersonic Speeds—Theory and Numerical Application. Jour. Aero. Sci., vol. 15, no. 6, June 1948, pp. 317-336.
- Morikawa, George K.: The Wing-Body Problem for Linearized Supersonic Flow. Calif. Inst. of Tech. Doctoral Thesis, 1949. GALCIT, Jet Propulsion Lab. PR4-116.
- Bolton-Shaw, B. W.: Wing-Body Interference at Supersonic Speeds—Rectangular Wing at Incidence on a Body at Zero Incidence. English Electric Co. Rep. LA. t. 039.
- Nielsen, Jack N., and Matteson, Frederick H.: Calculative Method for Estimating the Interference Pressure Field at Zero Lift on a Symmetrical Swept-Back Wing Mounted on a Circular Cylindrical Body. NACA RM A9E19, 1949.
- Nielsen, Jack N.: Supersonic Wing-Body Interference. Calif. Inst. of Tech. Doctoral Thesis, 1951.
- von Kármán, Theodore, and Moore, Norton B.: Resistance of Slender Bodies Moving With Supersonic Velocities, With Special Reference to Projectiles. Amer. Soc. Mech. Engrs., vol. 54, Dec. 1932, pp. 303-310.
- Phinney, R. E.: Wing-Body Interference. Progress Report No. 4.
   University of Michigan, Eng. Res. Inst., Project M937, April 1952.
- Nielsen, Jack N., and Pitts, William C.: Wing-Body Interference at Supersonic Speeds With an Application to Combinations With Rectangular Wings. NACA TN 2677, 1952.
- Bailey, H. E., and Phinney, R. E.: Wing-Body Interference. Final Report. Part I. Theoretical Investigation. University of Michigan, Eng. Res. Inst., 1937-1-F, Jan. 1954.
- Bailey, H. E., and Phinney, R. E.: Wing-Body Interference. Final Report. Part II. Experimental Investigation of Cylindrical Model. University of Michigan. Eng. Res. Inst., Feb. 1954.


- Pitts, William C., Nielsen, Jack N., and Gionfriddo, Maurice P.: Comparison Between Theory and Experiment for Interference Pressure Field Between Wing and Body at Supersonic Speeds. NACA TN 3128, 1954.
- Tsien, H.: Supersonic Flow Over an Inclined Body of Revolution. Jour. Aero. Sci., vol. 5, no. 12, 1938, pp. 480-483.
- Lagerstrom, P. A., and Van Dyke, Milton D.: General Considerations About Planar and Nonplanar Lifting Systems. Douglas Aircraft Co., Rep. No. SM-13432, June 1949.
- Ward, G. N.: The Approximate External and Internal Flow Past a Quasi-Cylindrical Tube Moving at Supersonic Speeds. Quart. Jour. Mech. and App. Math., vol. I, pt. 2, June 1948, pp. 225-245.
- Fraenkel, L. E.: On the Operational Form of the Linearized Equation of Supersonic Flow. Jour. Aero. Sci., vol. 20, no. 9, 1953, Readers Forum, pp. 647-648.
- Mersman, W. A.: Numerical Calculation of Certain Inverse Laplace Transforms. (Résumé) Vol. 2 of Proc. Intl. Cong. of Mathematicians, Amsterdam, 1954.
- Lamb, Horace: Hydrodynamics. Sixth Ed., Dover Publications, 1945. p. 527.
- Busemann, Adolf: Infinitesimal Conical Supersonic Flow. NACA TM 1100, 1947.
- Alden, Henry L., and Schindel, Leon H.: The Calculation of Wing Lift and Moments in Nonuniform Supersonic Flows. Meteor Rep. No. 53, M. I. T., May 1950.
- Cramer, R. H.: Interference Between Wing and Body at Supersonic Speeds. Part V—Phase I Wind-Tunnel Tests Correlated With the Linear Theory. Cornell Aero. Lab. Rep. No. CAL/CM-597, Dec. 1950.
- Lawrence, H. R., and Flax, A. H.: Wing-Body Interference at Subsonic and Supersonic Speeds. Survey and New Developments. Paper presented at the Annual Summer Meeting of the I. A. S., Los Angeles, July 15-17, 1953.
- Watson, G. N.: A Treatise on the Theory of Bessel Functions. Second Ed. 1944, MacMillan.
- Carslaw, H. S., and Jaeger, J. C.: Operational Methods in Applied Mathematics. Second Edition 1947, Oxford University Press.




(a)  $W_o(x,r)$   $0 \le x \le 2$  Chart 1.—Values of  $W_{2n}(x,r)$  functions.




(b)  $W_o(x,r)$   $2 \le x \le 4$  Chart 1.—Continued.




(c)  $W_2(x,r)$   $0 \le x \le 2$  Chart 1.—Continued.



(d)  $W_2(x,r)$   $2 \le x \le 4$  Chart 1.—Continued.



(e)  $W_4(x,r)$   $0 \le x \le 2$  Chart 1.—Continued.



(f)  $W_4(x,r)$   $2 \le x \le 4$  Chart 1.—Continued.




TABLE I.—VALUES OF M2n(x)

x	M <sub>o</sub> (x)	$M_2(x)$	M <sub>4</sub> (x)	$M_6(x)$
0	- &	œ	&	— œ
. 05			<b> 531</b>	<b> 716</b>
. 1	-1.321	<b>−. 787</b>	. 405	1. 334
. 15 . 2	868	166		1. 155
. 25	808	100	. 902	. 735 . 279
. 3		. 131	. 831	119
. 35		. 101	. 661	41 <b>7</b>
. 40	538	. 304	. 560	<b></b> 595
. 45				675
. 50			. 245	<b> 655</b>
. 6	<b> 378</b>	. 450	<b> 040</b>	<b>—. 417</b>
. 7		~	<b> 253</b>	070
. 75				. 095
. 8 . 85	292	. 457	<b> 386</b>	. 235
. 90 . 9			<b> 434</b>	. 340 . 406
. 9 . 95			404	. 400 . 433
1. 0	<b> 224</b>	. 392	<b> 412</b>	. 433 . 420
î. ĭ		. 552	337	. 306
1. 2	<b> 180</b>	. 294	231	. 123
1. 3			115	062
1. 4	<b> 147</b>	. 188	. 000	<b>—. 197</b>
1. 5			. 095	<b>−. 256</b>
1. 6	<b>−. 122</b>	. 088	. 163	−. <b>239</b>
1. 7			. 204	162
1. 8	<b> 102</b>	. 005	. 211	062
1. 9 2. 0	000		. 197	. 036
2. 0 2. 1	086	<b> 058</b>	. 164	. 105
2. 2	073	-, 100	. 069	. 1 <b>34</b> . 1 <b>2</b> 1
2. 3	019	100	. 020	. 085
2. 4	062	123	022	. 036
2. 5	. 552	. 120	053	013
2. 6	053	126	073	053
2. 7				<b> 063</b>
2. 8	<b> 045</b>	<b> 119</b>	080	059
2. 9			<b> 071</b>	042
3. 0	<b> 038</b>	<b> 103</b>	<b> 060</b>	019
3. 1			<b> 038</b>	. 005
3. 2	<b> 031</b>	083	019	. 022
3. 3 3. 4	006	061	002	. 030
3. <del>4</del> 3. 5	<b> 026</b>	061	. 011	. 028
3. 5 3. 6	022	040	. 021	. 019 . 008
3. 7	. 022	. 010	. 027	003 002
3. 8	018	022	. 025	011
3. 9		1	. 022	014
4. 0	016	007	. 015	103

NOTE that  $M_{2\pi}(x) \rightarrow -\frac{1}{\pi} \sqrt{\frac{2}{a}}$  as  $x \rightarrow 0$ .

#### TABLE II.—VELOCITY AMPLITUDE FUNCTIONS

	Angle of attack case, $f_{2n}(x)$ functions					Wing-incidence case, $f_{2n}(x)$ functions				
	$\frac{f_o}{V\alpha_B}$	$rac{f_2}{Vlpha_B}$	$rac{f_4}{Vlpha_B}$	$\frac{f_6}{Vlpha_B}$	$rac{f_8}{Vlpha_B}$	$\frac{f_{10}}{V lpha_B}$	$\frac{f_o}{Vi_W}$	$rac{f_2}{Vi_W}$	$rac{f_4}{Vi_W}$	$\frac{f_{6}}{Vi_{W}}$
	0	0	0	0	0	0	0	0	0	0
	. 001	. 003	. 001	. 003	. 003	. 004	. 0001	. 0003	. 0003	. 0003
- 1	. 003	. 008	. 004	. 007	. 005	. 007	. 0005	. 0010	. 0010	. 0010
1	. 006	. 012	. 008	. 011	. 009	. 012	. 0011	. 0023	. 0023	. 0022
- 1	. 008	. 017	. 013	. 015	. 013	. 016	. 0020	. 0040	. 0040	. 0038
- 1	. 011	. 022	. 019	. 015 . <b>020</b>	. 017	. 020	. 0032	. 0063	. 0061	. 0038 . 0058
- 1	. 014	. 029	. 026	. 025 . 031 . 037	. 022	. 022	. 0046	. 0091 . 0123	. 0087	. 0080
	. 019	. 037	. 034	. 031	. 027	. 024	. 0063	. 0123	. 0116	. 0104
	. 024	. 037 . 047	. 043	. 037	. 033	. 025	. 0082	. 0160	. 0148	. 0128
	. 029 . 032	. 057	. 052	. 044 . 052	. 037	. 024	. 0104	. 0201	. 0181	. 0151
-	. 032	. 068	. 062	. 052	. 040	. 023	. 0129	. 0247	. 0217	. 0171
- [-				~- <b></b>			. 0156	. 0297	. 0253	. 0187 . 0197
	. 050	. 097	. 083	. 063	. 038	. 014	. 0186	. 0350	. 0289	. 0197
-		107	100				. 0219	. 0408 . 0469	. 0324 . 0356	. 0201 . 0196 . 0181
1	. 068	. 127	. 103	. 067	. 026	007	. 0255	. 0533	. 0395	018
	. 079 . 089	. 143 . 161	. 112 . 120	. 067 . 065	. 017	022 041	. 0293 . 0335	. 0600	. 0412	015
	. 009	, 101	. 120	. 000	007	041	. 0379	. 0670	. 0432	. 0153
-	. 111	. 199	, 133	. 051	023	080	0427	. 0742	. 0445	. 006
1		. 100	, 100				. 0427 . 0478	. 0815	. 0450	<b> 000</b>
l	. 136	. 238	, 140	. 026 . 008	068	<b> 106</b>	, 0531	. 0890	. 0447	<b> 008</b> 1
١	. 151	. 258	. 139	. 008	<b> 090</b>	<b> 114</b>	, 0589	. 0966	. 0433	0177
ł							, 0649	. 1043	. 0408	0283
l							. 0714	. 1119	. 0371	0410
١	. 196	. 315	. 126	065	<b> 146</b>	121	. 0781	. 1195	. 0320	0530
l	. 214	. 333	. 116	<b> 086</b>	<b> 159</b>	<b> 114</b>	. 0853	. 1269	. 0254	0679
					170		. 0928	. 1342	. 0173 . 0074	0829 098
۱	. 299	. 369 . 388	, 088	−. 145 −. 175	178 182	082 054	. 1008 . 1092	. 1411 . 1477	00/4 0041	1142
l	. 208	. 388	. 069	175	!	034	. 1180	. 1539	0174	129'
١	. 308	. 420	. 016	236	1 <del>7</del> 6	. 047	. 1273	. 1596	0326	1446
	. 500	. 120	. 010	. 200		.011	. 1371	. 1646	0497	<b> 158</b> 3
	. 353	. 450	052	<b> 286</b>	142	. 119	. 1475	. 1688	0686	—. 1 <b>7</b> 03
		. 461					. 1584	. 1688 . 1722	0893	<b> 1808</b>
l			<b>-</b>		!		. 1689	1746	<b>—. 1118</b>	1870
	. 429	. 476	181 232	<b> 322</b>	<b> 012</b>	. 164	. 1820	. 1757 . 1755	<b> 1359</b>	189°
l	. 457	. 478		<b> 323</b>	. 075	. 163	. 1948	. 1755	1616	189
ı							. 2084	. 1737	1886	183
						~	. 2229	. 1701 . 1644	2164 2451	173 156
l	. 587	. 456	<b> 452</b>	212	. 235	. 027	. 2382 . 2546	. 1562	2738 2738	135 135
l		. 400	432	1	. 200	. 021	. 2722	1452	3021	106
ĺ	. 667	. 411	552	<b>109</b>	. 223	170	2912	. 1452 . 1308	3292	071
	. 001		. 002	. 103	. 220	. 1, 0	. 3118	. 1125	<b> 3539</b>	031
1							. 3342	. 0894	3751	. 013 . 060
l	. 812	. 280	<b>−. 673</b>	. 178	. 093	<b>−. 234</b>	. 3591	. 0603	3908	. 060
1		<del>-</del>					. 3871	. 0235	3983	. 107
ļ							. 4194	0237	3939	. 148
1	1. 013	. 004	<b>623</b>	. 397	263	. 062	. 4584	0865	3704	. 172
l	1. 121	250	510	. 378	340	$egin{array}{c} . \ 225 \ \ 0144 \end{array}$	. 5098	1777 4241	3121 $0849$	036
1	1. 375	669 651	053	025	0268 0289	0144 $0078$	. 6366	<b> 4244</b>	0049	050
	1. 385 1. 393	631 631	047 045	032 040	0289 0230	0108	i i			!
-	1. 402	613	045	045	0192	0118		i		
1	1. 410	592	048	047	0156	0152	ı			
1	1. 415	572	055	045	0166	0146	į.			
Ì	1. 421	<b> 550</b>	064	040	0199	<b>0122</b>	1	!		
ı	1. 424	<b> 527</b>	<b> 075</b>	<b>−. 035</b>	<b> 0224</b>	<b> 0115</b>				
١	1. 425	<b> 503</b>	<b> 084</b>	一. 033	<b> 0206</b>	0135				
1	1. 424	<b>−. 479</b>	<b> 088</b>	<b> 036</b>	<b> 0195</b>	<b> 0127</b>				1
١	1. 421	<b> 459</b>	<b> 087</b>	<b>−. 037</b>	<b>—. 0203</b>	<b> 0129</b>				
	1. 384	434	085	<b> 036</b>	<b> 0202</b>	<b> 0129</b>				
١	1. 356	<b>429</b>	085	<b>036</b>	0202	<b>0129</b>	1			
1	1. 337	42 <b>7</b>	085	<b>036</b>	0202	<b>0129</b>				
ĺ	1. 323 1. 314	426 425	085 085	036 036	<b>0202</b> <b>0202</b>	0129 0129				
	1. 114	- 4/5								

# REPORT 1252—NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

# TABLE III.—ORIFICE LOCATIONS ON WING AND BODY OF WING-BODY COMBINATION

[Dimensions in inches measured from wing leading edge]

y/a=1.020 (¹)	y/a = 1.253	y/a=1.916	y/a = 2.583	y/a = 3.916	θ=90°	θ=45°
0. 400 . 775 1. 150 1. 525 1. 900 2. 275 2. 650	0. 400 . 775 1. 150 1. 525 1. 900 2. 275 2. 650	0. 775 1. 150 1. 525 1. 900 2. 275 2. 650	0. 400 . 775 1. 150 1. 525 1. 900 2. 275 2. 650	1. 150 1. 525 1. 900 2. 275 2. 650	-0. 281 . 219 . 719 1. 219 1. 719 2. 219 2. 719 3. 219 3. 719	0. 468 . 968 1. 468 1. 968 2. 468 2. 968

a = 0.75 inch.

TABLE IV.—PRESSURE COEFFICIENTS  $\left(\frac{p-p_1}{q_o}\right)$ (a)  $M=1.48,R=1.5\times10^6$ 

208 221 186 1155 1141 1135 136 272 272 272 272 185 185 1149 1137 ွ CITTE 911111 1111111 TITI 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 | 128 |  $\alpha_B = 6^\circ$ 411111 111111111111111 911111 | TECCETT | TECCETT | 11111 TITETT 143 098 073 073 038 036 037 145 095 095 095 038 9111111 4111111 စ ợ i i i i i i | fifififi 111111 003 003 003 007 07 07 07 07 07 06 06 06 06 880000 qiiiiii 1111111 31111 0.054 0.055 111111111111111 THE 9 i i ΗÍ Ηİ 092 075 065 058 055 051 092 059 053 053 053 960 960 960 960 960 960 960 960 072 071 059 054 4555555 ွ ٦٠١١١١ 111111 111111 1111111 11111 PITTITI 11111 55558 9 I I I I I I 111111 311111 007 019 020 030 034 034 9899988 2888 ıi i 137 105 062 053 053 018 045 057 071 085 119 -5.7° 8888888 288222  $-1.9^{\circ}$ 5233338 150 170 170 170 170 170 -3.8° 158888E 552488845 555 128 128 128 128 128 128 128 138 032 072 130 130 130 ۱ 0 000 010 150 150 168 189 189 189 189 -5.70 7.25.28.25.28 150 150 150 150 150 22 178 178 100 969 86238 00 152 112 112 104 125  $-1.9^{\circ}$ 2822825 38888 002 005 005 005 110 120 120 120 886 110 110 148 128 106 136 136 230 125 125 1120 4435588 223 169 169 176 176 202 202 185 185 185 185 -3.8°  $-5.7^{\circ}$ 17228 22222222222 222222 000 000 003 003 003 003 174 174 177 178 5288258 888888 194 134 138 138 166 854448 123448 281 284 201 201 201 201 201 201 0 2521228 202282225 °6: 232 197 187 232 232 233 2252222 2252222 2252222  $\alpha_B = -4^\circ$ ī -3.8° 28822888 227456 227456 227456 227756 227756 227756 227756 227756 227756 227756 227756 227756 227756 227756 227756 227756 227756 227756  $-5.7^{\circ}$ 20002888888 200088 ၀  $-1.9^{\circ}$ 9 -3.8° 82488458 478 372 334 351 351 355 \$28888 8288828 8288828 88555445 88 456 386 386 354 8283328 2 8 8 8 8 E 33,33,23,35,33 88888888 240 044 073 044 074 075 045 04 222322 222322 88 28 28 28 28 28 28 28 28 28 **.** x/cStation y/s = 0.319y/s = 0.170y/a = 0.208y/s = 0.431y/s = 0.652 $\theta = 80$ °  $\theta = 45^{\circ}$ 

TABLE IV.—PRESSURE COEFFICIENTS  $\left(\frac{p-p_1}{q_o}\right)$ —Continued (b)  $M=1.46, R=1.2\times10^6$ 

	Station	y/s = 0.170.	y/s=0.208	y/s=0.319	1/8=0.431	y/s=0.652	°06-9	θ=45°
<u>*</u>	z¦c	0.133 258 383 383 608 638 638 638 750 750	. 133 . 258 . 258 . 383 . 633 . 759	255 3853 653 653 759	133 258 258 258 603 633 759	. 388 508 633 759	- 094 - 073 - 240 - 410 - 573 - 740 - 906 - 1 073 1 240	323 323 489 686 823 823 823
	-5.70	0. 622 475 405 415 434 434 439		.				262 357 453 421 368
8 - B	1	0. 510 356 333 331 351 375	252 252 253 253 253 253 253 253 253 253	388 349 329 329 329	535 473 410 361 304 264 279	3.36 2.23 2.23 2.23 2.23 2.23 2.23 2.23	2228 3228 3228 3228 196	88.83.83.83.83.83.83.83.83.83.83.83.83.8
	-1.9°	2322 272 272 283 289 299 299		.				246 246 315 317 299
	00 -5.7°	233 2233 2233 2233 2236 236 236 236 236			1		0014 0029 029 029 029 029 240 276 286 286 286	266 266 266 266 266
8	i i	453 0.352 363 . 295 328 . 255 317 . 244 335 . 259 344 . 282		<u> </u>		388 . 331 304 . 259 254 . 211 221 . 180 202 . 158	0003 026 026 058 316 376 376 3778 367 367 367 367 367	3.5412 3.3712 3.3712 3.154212
r <sub>n</sub> = -4°	-1.9°	2309 230 230 230 232 232				31 . 251 59 . 206 11 . 169 80 . 143 58 . 124	005 . 002 010 . 002 047 . 044 148 . 037 278 . 212 278 . 212 273 . 245 169 . 176	035 031 221 159 232 178 296 191 296 243 279 231
	00	0, 209 174 156 140 134 134	1			11.20 11.20 11.20 11.20 11.20		080 0055 1141 1136 1162 1195
	-5.70	0. 297 255 222 222 214 283 263	262 281 281 281 282 282 282	263 263 253 243 224 213	233 233 238 238 238 138 138	.314 .245 .189 .169	000 0020 198 252 282 289 289 122	256 277 284 287 287 287 287
α <sub>B</sub> =-2		0. 222 199 170 110 110 110 200	223 202 182 169 166 192 208	. 224 . 196 . 184 . 179	232 247 226 226 198 1152	194	002 103 179 122 133 133	026 161 163 177 211
20	-1.9° 0	0. 151 132 114 114 110 110	149 128 1118 1118 143 143	153 123 123 131 131	154 150 147 143 112 090	1128 1128 107 1088 0888	200000000000000000000000000000000000000	20.032
	00 -5.	0.096 0.081 0.074 0.067 0.063	088 077 070 070 070 070	093 080 073 069 072 068	0889 0889 071 071	088 071 065 054	0000 0000 0000 0000 0000 0000 0000 0000 0000	016 021 073 073 082 073
α <sub>B</sub> =0°	.5.70 -3.80	1.0 0.11 1.157 1.1 1.128 0.0 1.131 0.0 1.191 1.0	1893 488 1891	198 173 160 157 140	202 202 203 178 132 109	221 176 141 119	002 0 011 112 1151 151 169 204 088	111 111 118 145 183 191
0.	80 -1.90	1113 0.051 105 0.048 0.087 0.041 0.084 0.045 0.083 0.040 0.092 0.042	1112 201 208 208 208 200 200 200 200 200 200 200	112 103 101 101 106 106 106 107 109 109 109 109 109 109 109 109 109 109	135 128 128 128 128 128 128 128 128 128 128	147 115 095 078 078 067	003 .001 005 .001 058 .020 102 .039 113 .048 146 .059 093 .072	024 074 077 0077 000 100 143
	-5.7°	0.070 0.075 0.063 0.063 0.063 0.063	0653 0459 0459 041 041 040 041 060 041	061 084 053 088 049 090 048 094 051 101	062 . 112 062 . 111 060 . 101 059 . 109 048 . 088 037 . 068	069 . 137 064 . 103 044 . 079 037 . 061 032 . 063	01 - 003 - 003 01 - 005 20 - 042 39 - 078 45 - 080 48 - 109 72 - 064	011 . 009 034 . 052 035 . 059 041 . 074 044 . 090 058 . 133
a B	-3.8°	0.001 0.017 0.018 0.028 0.038		8 .023 0 .029 1 .042 7 .039	2 036 11 036 10 036 9 036 8 039 8 039	7 055 3 042 9 025 11 017	25 25 25 25 25 25 25 25 25 25 25 25 25 2	- 009 - 009 - 008 - 008 - 008 - 046
α <sub>B</sub> =2°	-1.90	-0.046 -0.34 029 017 013 010		0.029 0.029 0.012 0.006	- 023 - 023 - 025 - 025 - 014 - 013	011 012 017 017	0.0000000000000000000000000000000000000	10220
	00	-0.093 -0.078 -0.059 -0.050			078 079 070 070 070	074 059 060 060	0 0 000	
	-5.70	. 0.048 . 0023 . 0023 . 0019 . 019 . 019			018 012 027 027 027	982336	100000000000000000000000000000000000000	1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
$\alpha_B = 4^{\circ}$	80.80	0.093 -0.056 -0.056 -0.037 -0.019 -0.	0.020 0.020 0.020 0.020 0.020	0.069 0.024 0.0128 0.0128	2426625 2426625 2426625 2426 2426	034	0042	8566666 8566666
	-1.9° 0°	138 -0. 109 -0. 070 -1. 058 -1.	146 1116 074 074 1.0 062 1.0 057	1118 1118 1111 100 100 100 1118 1118 11	88882888 1111111	0.0000000000000000000000000000000000000	66632886666	000000000000000000000000000000000000000
	-5.70	1178 1178 1178 1174 1174 1174 1174 1174	11111111	25.55.55 1.0.00 1.0.000 1.0.0000	138 138 138 138 138 138 138	8118 118 100 100 100 100 100 100 100 100	983558	00000000000000000000000000000000000000
B	-3.8°	151 -0.186 098138 071113 048082 033065 031071	103 - 191 103 - 143 104 - 1043 1028 - 072 1029 - 077	090 142 090 143 056 107 032 085 021 073 018 047	0955 - 115 070 - 117 073 - 120 070 - 122 044 - 100 041 - 100 017 - 074	11111	111111	030 - 033 062 - 098 046 - 086 041 - 077 037 - 081
$\alpha_B = \theta^{\circ}$	-1.9°	231 - 0.231 - 1822 - 153 - 120 - 101 - 101 - 101 - 101	1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	22 23 24 25 25 25 25 25 25 25 25 25 25 25 25 25	25.1.1.06 20.1.1.06 20.1.1.06 20.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1	11111	111111	
	00	0.270 1.224 1.137 1.130	11.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1	111111111111111111111111111111111111111	111111111111111111111111111111111111111		1111111	010 1145 1145 1146 1153 1153

TABLE IV.—PRESSURE COEFFICIENTS  $\left(\frac{p-p_1}{q_o}\right)$ —Continued (c)  $M=1.48, R=0.9\times10^6$ 

	00	-0.248 202 168 151 126 095		- 234 - 202 - 185 - 178 - 135	25.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1	189 157 137 126 095	020 024 019 019 1123 101	066 156 103 103
. 9	-1.9°	-0.203 -0.203 -1.151 -1.140 -1.083	1. 183 1. 183 1. 183 1. 125 1. 111	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	111160	1.110 1.125 1.116 1.116		- 075 - 139 - 083 - 092 - 099
$\alpha_B=6^{\circ}$	-3.8°	0.160 0.183 0.1063 0.063 0.063	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	1.130	108		0.0000000000000000000000000000000000000	071 050 053 043
	-5.7°	-0.118 092 047 047 011		0.040				
	00	-0.171 -1141 -1128 -1166 -1086	- 1983 - 125 - 107 - 100 - 100	- 165 - 154 - 115 - 115 - 115	741.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	11.1.1.1.1.088	0 0 001 0 0027 0 078 0 119 0 119 0 088	
$\alpha_B = 4^{\circ}$	-1.9°	-0.127 -0.097 -0.058 -0.058	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	111111		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	000000000000000000000000000000000000000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
α B <sub>B</sub>	-3.8°	-0.089 -0.052 -0.024 -0.016	468 468 468 468 468 468 468 468 468 468	0.000		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	. 0052
	-5.7°	-0.046 -0.019 -0.015 -0.015 -0.030	1	006 .022 .033 .035	020 020 027 027	. 028 829 829 829 101 101 101 101	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
	00	-0.093 -0.076 -0.076 -0.056 -0.057				0.066		. 021 - 054 - 053 - 058
20	-1.9°	-0.049 035 019 015	047 034 021 015	- 035 - 019 - 013 - 012	1	012 016 016	000 000 000 000 000 000 000 000 000 00	014 018 017 014
$\alpha_B = 2^\circ$	-3.8°	0.002 .015 .014 .023 .029 .028	.004 .021 .027 .027 .039		040 040 040 040 040 040 040	988.05.05.05.05.05.05.05.05.05.05.05.05.05.	003 003 017 017 017 054 064	. 010 . 010 . 024 . 033
	-5.7°	0.067 .073 .066 .066 .070 .070	. 068 . 070 . 072 . 073 . 073 . 090	. 093 . 093 . 095 . 073		. 089 . 089 . 065 . 065	. 009 . 018 . 017 . 024 . 024 . 161 . 161 . 063	. 013 . 063 . 069 . 107 . 122
	-1.9°	0.054 .047 .040 .046 .047	042 047 047 048 048			. 061 . 057 . 038 . 038	.001 .0020 .0220 .020 .020 .030 .030	. 024 . 024 . 042 . 041 . 041
α <sub>B</sub> =0°	9.80	0.121 .111 .092 .091 .102 .103		. 125 . 115 . 113 . 116 . 103	. 134 . 132 . 140 . 116 . 092	. 131 . 114 . 097 . 069	.005 .025 .032 .030 .030 .115 .115 .165	. 028 . 033 . 091 . 084 . 117
	-5.7°	0. 202 162 135 133 141 165	177 168 154 142 149 162	. 198 . 178 . 171 . 171 . 141	212 215 212 212 163 163	. 196 . 173 . 140 . 102	.013 .033 .033 .038 .038 .137 .197 .204	
	0	0. 100 . 086 . 072 . 070 . 063 . 065	988 970 170 170 170 170 170 170 170 170 170 1		28.09.09.09.09.09.09.09.09.09.09.09.09.09.	250 260 260 260 260	.001 .007 .028 .038 .043 .059	982.0.064
'B=-2°	-1.9°	0.167 1.183 1.181 1.121 1.132	150 132 132 121 118 118	. 157 . 144 . 137 . 136 . 119	158 1158 1165 1104	142	. 006 . 048 . 048 . 048 . 133 . 154 . 173	
α <sup>B</sup>	-3.8°	0. 252 211 . 177 . 171 . 182 . 202 . 202 . 186	. 235 . 215 . 191 . 178 . 185 . 192	. 233 . 214 . 202 . 166	245 250 240 240 1147	219 196 135 135	. 010 . 050 . 056 . 062 . 165 . 218 . 248 . 248 . 218	
	-5.7°	0. 320 0. 320 2. 223 2. 250 2. 251 2. 251	253 253 253 253 253	. 238 . 276 . 238 . 238 . 193		. 289 . 239 . 169 . 151	019 053 058 058 058 144 144 302 302 302 302 303 109	226 226 273 273 230
	0	0.218 0.218 1.148 1.146 1.172	150 1160 1160 1160 1160	191 167		163		046 158 1138 169
-40	-1.9	0.288 220 220 220 221 221 232	208. 228. 228. 208. 208. 208. 208. 208.	255 234 238 224 188 167	259 2259 163 163 145	236	900 900 900 900 900 900 900 900 900 900	250 211 212 212 212
α <sub>B</sub> ≡.	-3.8°	0.379 .300 .263 .273 .284	286 287 288 289 289 279 279	3321	359 359 310 310 3243 310 310	. 311 . 260 . 217 . 217 . 186		
	-5.7°	348 348 348 348 348 348 348 348 348 348	355 337 337 337 337	353	283. 2848	22,25,33	201 201 201 201 202 202 202 202 202 202	376
	00	0.332 44 . 258 224 . 224 7 . 251 8 . 227	8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	282 3 280 3 240 5 240 5 188	202 202 272 8 213 6 178	254 22, 224 1, 186 1, 160	2 012 2 076 2 086 7 207 7 207 8 239 8 239 9 178	3 .057 7 .079 8 .248 4 .273
$\alpha_B = -6^\circ$	-1.9°	25 0. 421 244 294 324 308 312 307	23.338 33.338 33.53 33.5	323 323 323 323 323 7	11 . 417 0 . 375 0 . 375 1 . 258 6 . 225 7 . 221	0 .323 6 .272 2 .226 6 .197 1 .181	10.061 10.067 10.067 13.297 14.320 189	2
a <sub>B</sub>	-3.80	22 0.525 26 .408 374 .374 86 .370	286 . 494 287 395 371 372 332 332		125 4 4 6 6 6 8 6 1 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	22 . 370 3 . 272 4 . 246 9 . 241	25 203 204 20 20 20 20 20 20 20 20 20 20 20 20 20	2672 2672 31 . 408 31 . 374 44 . 312
	-5.7°	288888888 2662 2663 2644 266888 2888	28 28 28 28 28 28 28 28 28 28 28 28 28 2	88 . 526 88 . 449 89 . 395 4 . 372	25.5 4.79 25.380 25.380 25.380 25.380 25.380 25.380	33 . 422 33 . 343 44 . 319	27.5 27.5 27.5 27.5 27.5 27.5 27.5 27.5	28 2 4 2 3 4 4 1 3 3 4 4 1 1 3 3 4 4 1 1 3 3 4 4 1 1 3 4 4 1 1 1 3 4 4 1 1 1 1
<b>≱</b>	z/c	0.133 2883 508 508 759 884	. 133 . 258 . 258 . 508 . 508 . 759 . 884	. 258 . 383 . 508 . 759	. 133 . 383 . 383 . 508 . 759 . 759	.383 .633 .759 .884	- 094 - 073 - 240 - 573 - 573 - 740 - 1073 1 240	. 156 . 323 . 489 . 656 . 823 . 823 . 823
10000		70	90	6	1	2		
<b>.</b>		y/s = 0.170.	y/s = 0.308.	y/s=0.319.	y/s=0.431	y/e ≠ 0.652		0=46°.
					1			

 $\begin{array}{l} {\rm fABLE\ IV.--PRESSURE\ COEFFICIENTS\ } \left(\frac{p-p_1}{q_o}\right) - {\rm Concluded} \\ {\rm (d)\ } \textit{M=2.00, R=1.5\times10^6} \end{array}$ 

	0,0	-0.187 -1.165 -1.133 -1.119 -1.066	1.186 1.177 1.162 1.129 1.118	11.11.1 22.22.22 22.22.22	1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	11128	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	111111 2001 2011 2011 2011 2011
9	-1.9°	0. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	111111	111111111111111111111111111111111111111	111111111111111111111111111111111111111	1 1 1 1 1 8 8 2 4 4 4 2 5	0.0000000000000000000000000000000000000	
α <sub>B</sub> =β°	-3.8°	- 0.148 - 1.124 - 0.072 - 0.061	11.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1	1.108	070 074 088 088 088 088 088 088 088 088 088 08			000000000000000000000000000000000000000
	-5.7°	0.123 0.088 0.085 0.041 0.041		072 078 072 065		033 035 037 038		1   1   1   1   1   1   1   1   1   1
	8		. 132 . 1122 . 110 . 007 . 079 . 073			080	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0.000
9,	-1.9	-0.107 080 082 062 049	111111 0000 0000 0000 0000 0000 0000 0	080 0082 072 00083 0083			000 011 011 011 011 000 000 000	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0
α <sub>B</sub> =4°	-3.8°	-0.080 -0.059 -0.037 -0.025	076 056 056 056 056 056 056	040			007 013 010 024 028 038	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0
	-5.70	0.050	7.00 20 20 20 20 20 20 20 20 20 20 20 20 2	013 013 007 004	0.009	.008 .005 .003	000000000000000000000000000000000000000	000000000000000000000000000000000000000
	00	0.072 - 0.048 - 0.046 - 0.046		062 061 053 050 047		048 048 049		
2.	-1.90	0.040	0.015 0.015 0.015 0.015 0.015			013 015 016		010.010.000
a = 2°	-3.8°	0.010 .002 .010 .011 .013	002 003 005 005 013 015	. 013 . 013 . 015 . 016 . 019	023 023 022 023 021 020	028 023 022 020 020	004 004 009 009 013 013 020 020	0 000 000 013 013
	-5.70	0.024 .030 .034 .035 .035	027 028 030 032 035 038	049 .047 .050 .050 .050	. 060 . 059 . 059 . 057 . 057 . 056	.063 .058 .058	000 010 010 022 039 048 048	002 . 024 . 029 . 033 . 035
	-1.9	0.035 .033 .030 .028 .028	034 029 027 027 028	038 034 034 032	. 037 . 039 . 039 . 039 . 038	.036 .035 .035 .033	0 003 . 007 . 004 . 024 . 032	006 007 028 028 024
$\alpha_B=0^\circ$	-3.80	0.072 .069 .053 .061 .067	. 063 . 063 . 064 . 056 . 056	. 081 . 073 . 070 . 065	. 079 . 081 . 080 . 077 . 074	.080 .078 .076	001 007 013 008 015 070 073	009 044 063 048 048
8	-5.70	0.113 .106 .097 .087 .081 .077	. 113 . 106 . 098 . 084 . 082 . 079	121 121 113 108 102 098	125 125 126 123 119 119	. 123 . 122 . 122 . 118	- 001 0 .009 .016 .021 .061 .103	.011 .016 .077 .074 .069
	0	0.077 .070 .057 .056 .051 .045	970 989 989 950 950 950	060 060 067 061 046	.055 .053 .057 .057 .056 .056	. 052 . 052 . 052 . 050	. 008 . 002 . 007 . 015 . 011 . 052 . 059	. 009 . 016 . 054 . 043
-2°	-1.9	0.116 .085 .089 .080 .074	118 105 097 091 086 088 075	103 103 099 091 079	090 090 090 090 090 090	.093 .093 .093 .088	. 007 . 007 . 020 . 021 . 011 . 080 . 084	016 042 072 072 063
α <sub>B</sub> ==	-3.8°	0.164 .150 .124 .124 .103	484 128 119 119 110 105	158 141 132 122 115 115	146 147 151 139 139	144 140 142 138	.007 .007 .012 .028 .025 .068 .115	. 022 . 022 . 106 . 077
	-5.70	0. 211 . 192 . 161 . 152 . 136 . 128	212 191 175 161 160 150	. 209 . 197 . 172 . 160 . 150	202 193 193 163 163	. 195 . 191 . 193 . 186 . 174	. 008 . 008 . 022 . 032 . 031 . 118 . 155 . 166	. 027 . 030 . 125 . 130 . 120
	0	0.149 .129 .129 .103 .088	91.08 91.09 10.00	135 124 113 113 104	116 118 123 120 120 116	112	. 020 . 020 . 011 . 023 . 054 . 090 . 100	000 000 000 000 000 000 000 000 000 00
-40	-1.9°	0. 196 . 183 . 157 . 150 . 136 . 128	206 166 152 137 137 137	186 180 165 171 171 130	162 163 171 171 165 165 167	152	. 019 . 018 . 014 . 039 . 046 . 145 . 139	000 000 1116 1116 1116
a <sub>B</sub> =	-3.8°	0. 247 230 197 184 168 157	262 225 207 189 178 170	242 227 208 179 179	222 224 224 224 224 224 224 224 224	222.23.1.	. 020 . 018 . 014 . 031 . 046 . 126 . 180 . 180	. 026 . 062 . 138 . 141 . 141
	-5.70	0.288 .268 .231 .218 .198	226 226 226 226 226 226 226 226 226 226	222	25.22.23.25.25.25.25.25.25.25.25.25.25.25.25.25.	22.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2	.022 .022 .016 .027 .134 .198 .213	003 140 140 170 170 170
	0	0. 231 214 191 174 150 150	236 204 177 177 169 161	208 177 191 161 161	182 182 192 176 176 166	173 182 183 171	. 040 . 033 . 027 . 028 . 039 . 066 . 154	. 003 . 032 . 137 . 138 . 138
.9-	-1.99							
i a	-3.8°	0. 337 286 286 228 228 218	E8827.08	25 25 25 25 25 25 25 25 25 25 25 25 25 2	258 288 288 288 288 288 288 288 288 288	888888 888888	033 028 042 073 073 195 239 242 242 233 233	175 175 1985 200
	-5.70	0.30 358. 282. 282. 283. 283. 283. 283. 283.	347 347 316 316 223 249 249	262	363 365 375 331 314	356 359 359 317		. 004 . 108 . 217 . 257
<u>k</u>		0. 133 258 383 508 633 759	258 383 508 759 884 759	258 383 508 759 884 884	258 388 508 847 888 888 888 888	88.83.55 88.83.54 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 88.83 883	- 094 . 240 . 573 . 740 . 906 . 906 . 1.073	25. 25. 25. 25. 25. 25. 25. 25. 25. 25.
	x/c							
	Station	y/a=0.170	y/e=0.208.	y/s=0.319	y/s=0.431	y/s=0.652	θ=80°	0=45°